

Code No.	Item Description	UNIT	URBAN TOTAL QUANTITIES	100% STATE		CONSTRUCTION TYPE CODE			
				ROADWAY	TRAFFIC SIGNAL	Y080	LIGHTING	TRAF SURV.	
				J080-2A	Y031-IF	ELMHURST	Y030-IE	Y032-IF	
						100%			
60258000	MANHOLES TO BE RECONSTRUCTED (SPECIAL)	EACH	1	1					
60261540	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1					
60500040	REMOVING MANHOLES	EACH	3	3					
60500050	REMOVING CATCH BASINS	EACH	4	4					
60500060	REMOVING INLETS	EACH	14	14					
60500065	REMOVING INLETS, SPECIAL	EACH	5	5					
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	5	5					
60600605	CONCRETE CURB, TYPE B	FOOT	2,420	2,420					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2,764	2,764					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	8,683	8,683					
60618320	CONCRETE MEDIAN SURFACE, 6 INCH	SQ FT	5,238	5,238					
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	91	91					
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	6,750	6,750					
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	769	769					
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2					
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2					
63200310	GUARDRAIL REMOVAL	FOOT	4,210	4,210					
66400305	CHAIN LINK FENCE, 6'	FOOT	5,828	5,828					
66407600	CHAIN LINK GATES, 6' X 12' DOUBLE	EACH	1	1					
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1	1					
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1					
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1					
67100100	MOBILIZATION	L SUM	1	1					
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	0.8	0.1		0.1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60	60					
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	109	109					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	12,895	12,895					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,830	1,830					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	45	45					
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	290	290					

LOCATION OF WORK:
F.A.U. 3537 - U.S. 20 (LAKE STREET)
WALNUT STREET TO YORK STREET
DUPAGE COUNTY

* SPECIALITY ITEM

FILE NAME *
Quant_SHT_ALL.dgn

USER NAME * Matt Rempler 100T V8	DESIGNED -	REVISED -
	DRAWN - DR	REVISED -
PLOT SCALE * 50.0000' / 1" IN.	CHECKED - SRG	REVISED -
PLOT DATE * 5/7/2010	DATE - 1/18/10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: N.T.S.	SHEET NO. 4 OF	SHEETS	STA. N/A TO STA. N/A

F.A.U. RTE. 3537	SECTION (4Y & 22-3)R-2	COUNTY DUPAGE	TOTAL SHEETS 284	SHEET NO. 7
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 62093