

Code No.	Item Description	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
				100% STATE		100% STATE		
				ROADWAY J000-2A	TRAFFIC SIGNAL Y031-IF	Y000 ELMHURST 100%	LIGHTING Y030-IE	TRAF SURV. Y032-IF
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	3				3	
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	5				5	
* 84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	2				2	
* 84400205	RELOCATE EXISTING LIGHT TOWER	EACH	7				7	
* 85000100	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	WEEK	2		2			
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2		2			
* 86400100	TRANSCEIVER-FIBER OPTIC	EACH	2		2			
* 87000150	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 6 AND NO. 8 GROUND	FOOT	618					618
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	457		457			
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,736		1,736			
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3,316		3,316			
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2,234		2,234			
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2,862		2,862			
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	34		34			
* 87302245	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 5C	FOOT	165		165			
* 87302255	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 7C	FOOT	230		230			
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	5		5			
* 87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	1		1			
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		2			
* 87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1		1			
* 87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	2		2			
* 87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1		1			
* 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1		1			
* 87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1		1			
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	32		32			
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8		8			
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	45		45			
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	45		45			
* 87900200	DRILL EXISTING HANDHOLE	EACH	1		1			
* 88030010	SIGNAL HEAD, LED, 1-FACE, 1-SECTION, MAST-ARM MOUNTED	EACH	2		2			
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8		8			

LOCATION OF WORK:
F.A.U. 3537 - U.S. 20 (LAKE STREET)
WALNUT STREET TO YORK STREET
DUPAGE COUNTY

* SPECIALITY ITEM

FILE NAME =
Quant_SHT_ALL.dgn

USER NAME = Matt Rampfer IDOT V8	DESIGNED -	REVISED -
PLOT SCALE = 50.0000 1/16"	DRAWN - DR	REVISED -
PLOT DATE = 5/6/2010	CHECKED - SRG	REVISED -
	DATE - 1/18/10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: N.T.S.	SHEET NO. 4 OF	SHEETS	STA. N/A TO STA. N/A

F.A.U. RTE. 3537	SECTION 4Y & 22-31R-2	COUNTY DUPAGE	TOTAL SHEETS 284	SHEET NO. 10
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 62093	