

ROADWAY REMOVAL QUANTITIES

LOCATION	ROAD	STATION	STATION	PAVEMENT	HOT-MIX	DRIVEWAY	SIDEWALK	COMB	PAVED	MEDIAN	GUARDRAIL	FENCE	REMOVE
				REMOVAL	ASPHALT	PAVEMENT	REMOVAL	C & G	SHOULDER	REMOVAL	REMOVAL	REMOVAL	OVERHEAD
				SQ. YD.	SQ. YD.	SQ. YD.	SQ. FT.	FOOT	SQ. YD.	SQ. FT.	FOOT	FOOT	STRUCTURE
													- SPAN
													EACH
U.S. 20 (LAKE ST.)		355+65 TO 384+00		2444.0	0.0	0.0	0.0	1667.0	288.0	1685.0	260.0	835.0	0.0
		364+00 TO 379+00		4828.0	0.0	0.0	0.0	3320.0	187.0	4830.0	495.0	1515.0	1.0
		379+00 to 388+51.08		3634.0	328.0	0.0	0.0	2657.0	378.0	10099.0	855.0	980.0	0.0
		SUBTOTAL		10906.0	328.0	0.0	0.0	7644.0	851.0	16614.0	1610.0	3340.0	1.0
Ramp E		0+00 TO 4+00		1089.0	0.0	0.0	0.0	800.0	0.0	0.0	0.0	400.0	0.0
		4+00 TO 10+003		2849.0	0.0	0.0	0.0	170.0	1376.0	0.0	1415.0	260.0	0.0
		SUBTOTAL		3938.0	0.0	0.0	0.0	970.0	1376.0	0.0	1415.0	660.0	0.0
Ramp O (Ramp F)		1+00 TO 3+00		3013.0	0.0	0.0	0.0	0.0	1386.0	0.0	607.0	0.0	0.0
		3+00 to 14+00		4477.0	0.0	0.0	0.0	55.0	2470.0	0.0	313.0	0.0	0.0
		SUBTOTAL		7490.0	0.0	0.0	0.0	55.0	3856.0	0.0	920.0	0.0	0.0
York Road		40+08 TO 46+31		428.0	3655.0	341.0	2875.0	1170.0	0.0	233.0	265.0	0.0	0.0
Construction Staging		PRESTAGE		6355.0	0.0	0.0	0.0	0.0	0.0	2970.0	0.0	0.0	0.0
		STAGE I		1534.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
		STAGE II		1259.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
		STAGE III		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
		SUBTOTAL		9148.0	0.0	0.0	0.0	0.0	0.0	2970.0	0.0	0.0	0.0
		TOTAL		31910.0	3983.0	341.0	2875.0	9839.0	6083.0	19817.0	4210.0	4000.0	1.0

ROADWAY QUANTITIES

LOCATION	ROAD	STATION	AGGREGATE	PCC	TEMPORARY	PCC	PCC	PROTECTIVE	PCC	PCC	POLYMERIZED	POLYMERIZED	HOT-MIX	LEVELING	BITUMINOUS	STRIP	AGGREGATE	COMB	COMB	CONCRETE	CONCRETE	CONCRETE	CONCRETE
			SUBGRADE	BASE	PAVEMENT	PAVEMENT	COAT	DRIVEWAY	SIDEWALK	HOT-MIX	HOT-MIX	ASPHALT	ASPHALT	ASPHALT	BINDER	MATERIAL	REFLECTIVE	SHOULDERS	CONCRETE	CONCRETE	CONCRETE	CONCRETE	CONCRETE
			12"	COURSE		(JOINTED)	10 1/4"		8"	5"	MIX "F", N90	MIX "F", N90	COURSE 4 1/2"	(MACHINE METHOD) N70	(PRIME COAT)	CRACK CONTROL TREATMENT	TYPE B	C & G TYPE B-6.12	C & G TYPE B-6.24	CURB TYPE B	MEDIAN TYPE SB-6.12	MEDIAN TYPE SB-6.24	MEDIAN SURFACE 6"
			SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. FT.	TON	TON	SQ. YD.	TON	TON	FOOT	TON	FOOT	FOOT	FOOT	SQ. FT.	SQ. FT.	SQ. FT.
U.S. 20 (LAKE ST.)		355+65 TO 384+00	5476.0	0.0	0.0	4031.0	746.0	5537.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	117.0	120.0	2765.0	240.0	0.0	210.0	240.0
		364+00 TO 379+00	12415.0	0.0	0.0	9176.0	1181.0	12193.0	0.0	0.0	69.3	59.4	707.0	0.0	1.0	0.0	316.0	1402.0	3753.0	2180.0	0.0	1638.0	2180.0
		379+00 to 388+51.08	5071.0	0.0	0.0	4002.0	490.0	5447.0	0.0	0.0	123.3	26.3	0.0	106.0	0.0	257.0	115.0	576.0	1497.0	0.0	0.0	1932.0	1755.0
		SUBTOTAL	22962.0	0.0	0.0	17209.0	2417.0	23177.0	0.0	0.0	192.6	85.7	707.0	106.0	1.0	257.0	548.0	2098.0	8015.0	2420.0	0.0	3780.0	4175.0
Ramp E		0+00 TO 4+00	908.0	0.0	0.0	667.0	142.0	910.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	21.0	0.0	363.0	0.0	0.0	0.0	0.0
		4+00 TO 10+00	2151.0	0.0	0.0	1885.0	943.0	2828.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	125.0	0.0	0.0	0.0	0.0	0.0	0.0
		SUBTOTAL	3059.0	0.0	0.0	2552.0	1085.0	3738.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	146.0	0.0	363.0	0.0	0.0	0.0	0.0
Ramp F		1+00 TO 3+00	1492.0	0.0	0.0	1157.0	278.0	1489.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	203.3	0.0	70.0	0.0	0.0	0.0	275.0
		3+00 to 14+00	5436.0	0.0	0.0	3543.0	1893.0	5436.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	320.0	0.0	0.0	0.0	0.0	0.0	0.0
		SUBTOTAL	6928.0	0.0	0.0	4700.0	2171.0	6925.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	523.3	0.0	70.0	0.0	0.0	0.0	275.0
York Road		40+08 TO 46+31	609.0	415.0	0.0	0.0	44.0	685.0	287.0	3012.0	375.6	321.9	0.0	0.0	0.0	1521.0	0.0	666.0	200.0	0.0	91.0	0.0	788.0
Construction Staging		PRESTAGE	0.0	0.0	6355.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2970.0	0.0
		STAGE I	0.0	0.0	1534.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
		STAGE II	0.0	0.0	1259.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
		STAGE III	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
		SUBTOTAL	0.0	0.0	9148.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2970.0	0.0
		TOTAL	33558.0	415.0	9148.0	24461.0	5717.0	34525.0	287.0	3012.0	568.2	408.0	707.0	106.0	1.0	1778.0	1217.0	2764.0	8683.0	2420.0	91.0	6750.0	5238.0