

DRAINAGE REMOVAL QUANTITIES

LOCATION		STORM SEWER REMOVAL 10"	STORM SEWER REMOVAL 12"	STORM SEWER REMOVAL 15"	PIPE CULVERT REMOVAL	BOX CULVERT REMOVAL	MANHOLES TO BE ADJUSTED	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS	PAVED DITCH REMOVAL	INLETS TO BE ADJ WITH NEW FRAME	REMOVING INLETS SPECIAL	DOM. WATER SERVICE BOX TO BE ADJUSTED	WATER & VALVES TO BE ADJUSTED	FIRE HYDRANTS TO BE MOVED
ROAD	STATION	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	FOOT	EACH	EACH	EACH	EACH	EACH
U.S. 20 (LAKE ST.)	355+65 TO 364+00	0.0	535.0	40.0	0.0	0.0	0.0	3.0	1.0	5.0	0.0	0.0	1.0	0.0	0.0	0.0
	364+00 TO 379+00	0.0	147.0	128.0	50.0	0.0	0.0	1.0	1.0	2.0	0.0	0.0	4.0	0.0	0.0	0.0
	379+00 to 388+51.08	0.0	180.0	90.0	0.0	120.0	0.0	2.0	2.0	4.0	227.0	0.0	0.0	0.0	0.0	0.0
	SUBTOTAL	0.0	862.0	258.0	50.0	120.0	0.0	6.0	4.0	11.0	227.0	0.0	5.0	0.0	0.0	0.0
Ramp E	0+00 TO 4+00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	4+00 TO 10+00	0.0	0.0	0.0	58.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	SUBTOTAL	0.0	0.0	0.0	58.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Ramp O (Ramp F)	1+00 TO 3+00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	3+00 to 14+00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1.0
	SUBTOTAL	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1.0
York Road	40+08 TO 46+31	53.0	20.0	244.0	0.0	0.0	5.0	3.0	0.0	3.0	0.0	1.0	0.0	5.0	5.0	2.0
Construction Staging	PRESTAGE	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	STAGE I	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	STAGE II	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	STAGE III	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	SUBTOTAL	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
TOTAL		53.0	882.0	502.0	108.0	120.0	5.0	3.0	4.0	14.0	227.0	1.0	5.0	5.0	5.0	3.0

PATCHING QUANTITIES

LOCATION		CLASS D PATCHES TYPE II 8 INCH	CLASS D PATCHES TYPE III 8 INCH	CLASS D PATCHES TYPE IV 8 INCH	HOT-MIX ASPHALT REMOVAL OVER PATCHES 3"	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES
ROAD	STATION	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	TON
U.S. 20 (LAKE ST.)	360+70 Rt.	0.0	16.7	0.0	20.0	3.3
	364+30 to 366+05 Rt.	0.0	0.0	122.4	137.5	22.7
	SUBTOTAL	0.0	16.7	122.4	157.5	26.0
York Road	41+18 Lt. to 41+25 Rt.	0.0	0.0	25.0	30.0	5.0
	43+97 to 43+90 Rt.	11.1	0.0	0.0	13.3	2.2
	SUBTOTAL	11.1	0.0	25.0	43.3	7.2
TOTAL		11.0	17.0	147.0	201.0	33.0

FENCE QUANTITIES

LOCATION		CHAIN LINK FENCE, 6'	CHAIN LINK GATE 6'x12' DBL	ORNAMENTAL FENCE
ROAD	STATION	LF	EACH	LF
U.S. 20 (LAKE ST.)	355+65 to 364+00 Rt	715	0	0
	361+20 to 364+00 Lt	280	0	0
	364+00 to 367+00 Lt	300	0	0
	364+00 to 376+40 Rt	150	0	0
	369+00 to 379+00 Lt	1000	0	0
	377+00 to 379+00 Rt	0	0	200
	379+00 to 383+70 Lt	470	0	0
	379+00 to 384+85 Rt	0	0	585
	385+20 to 388+50 Lt	330	0	0
	387+40 to 390+00 Rt	260	0	0
	SUBTOTAL	3505	0	785
	Ramp E	0+00 to 10+00 Lt	1000	0
5+75 to 10+00 Rt		480	0	0
SUBTOTAL		1480	0	0
Ramp F	1+60 to 3+00 Lt	140	0	0
	2+30 to 3+00 Rt	95	0	0
	SUBTOTAL	235	0	0
York Road	45+45 to 46+88 Rt	143	0	0
	46+88 to 47+10 Rt	0	1	0
	47+10 to 48+70 Rt	160	0	0
	46+35 to 49+10 Lt	305	0	0
	SUBTOTAL	608	1	0
TOTAL	5828	1	800	

NOTE: ACCESS CONTROL FENCE WILL BE PAID FOR AS CHAIN LINK FENCE, 6'

FILE NAME = Drain_remv_misc.dgn	USER NAME = IDDT(eng)	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.U. RTE. 3537	SECTION (4Y & 22-3)R-2	COUNTY DUPAGE	TOTAL SHEETS 284	SHEET NO. 37			
PLOT SCALE = 50.0000' / in.		CHECKED - SRG	REVISED -	SCALE: N.T.S.		SHEET NO. 37 OF		SHEETS		STA. N/A	TO STA. N/A	CONTRACT NO. 62093	
PLOT DATE = 3/23/2018		DATE - 1/18/10	REVISED -			FED. ROAD DIST. NO.					ILLINOIS FED. AID PROJECT		