

EXISTING SIGN REMOVAL																
EXISTING LOCATION	DIRECTION OF TRAVEL	SIGN NUMBER	WIDTH FT	DEPTH FT	SIGN AREA SF	SIGNS						RELOCATE SIGN PANEL ASSEMBLY, EA	REMOVE OVERHEAD STRUCTURE - SPAN, EA	REMOVE GROUND MOUNT SIGN SUPPORT, EA	REMOVE CONCRETE FOUNDATION - GROUND MOUNT, EA	
						REMOVE SIGN PANEL			REMOVE SIGN PANEL ASSEMBLY		TYPE A EA					TYPE B EA
						TYPE 1	TYPE 2	TYPE 3	TYPE A EA	TYPE B EA						
356+10 L	EB	R4-7 R3-4	3.00 3.00	4.00 3.00	12.00 9.00		12.00			1						
356+10 R	EB	R2-1	2.50	3.00	7.50	7.50			1							
360+00 R	EB	GUIDE	10.00	6.00	60.00		60.00					1	1			
362+75 L	EB	GUIDE	10.00	6.00	60.00		60.00					1	1			
366+00	EB	OVERHEAD			0.00	0.00						1				
368+25 L	EB	W12-1	3.00	3.00	9.00	9.00			1							
369+00	EB	M3-2 M1-100 M4-4 M6-2L	2.00 2.00 2.00 1.75	1.00 2.00 1.00 1.25	2.000 4.000 2.000 2.188	2.00 4.00 2.00 2.19			1							
370+30	EB	W1-4L	3.00	3.00	9.00	9.00			1							
371+30	EB	W1-8	1.75	3.00	5.250	5.25			1							
372+20	EB	W1-8	1.75	3.00	5.250	5.25			1							
FROM EX. I/S		W3-1A	3.00	3.00	9.00	9.00			1							
FROM EX. I/S		R5-1A	3.00	2.00	6.00	6.00			1							
FROM EX. I/S		W1-8 R5-1A	1.75 3.00	3.00 2.00	5.250 6.000	5.25 6.00			1							
FROM EX. I/S		R3-2	3.00	3.00	9.00	9.00			1							
FROM EX. I/S		M3-4 M1-4 M6-3 M3-2 M1-4 M6-1R M3-2A M1-1 M6-1RA SHOULDER	2.00 2.00 1.75 2.00 2.00 1.75 2.00 2.50 1.75 2.00	1.00 2.00 1.25 1.00 2.00 1.25 1.00 2.00 1.25 2.00	2.000 4.000 2.188 2.000 4.000 2.188 2.000 5.000 2.188 4.000	2.00 4.00 2.19 2.00 4.00 2.19 2.00 5.00 2.19 4.00			1							
FROM EX. I/S		R3-8	3.00	2.50	7.50	7.50			1							
FROM EX. I/S		D1-2A	6.00	4.00	24.00		24.00					1	1			
FROM EX. I/S		M3-4 M1-4 D1-1C M6-3 M3-2 M1-4 D1-1C M5-1R	2.00 2.00 2.00 1.75 2.00 2.00 1.00 1.75	1.00 2.00 1.00 1.25 1.00 2.00 2.00 1.25	2.000 4.000 2.000 2.188 2.000 4.000 2.000 2.188	2.00 4.00 2.00 2.19 2.00 4.00 2.00 2.19			1							
FROM EX. I/S		R5-1100	4.00	4.50	18.00		18.00			1						
FROM EX. I/S		W4-3	4.00	4.00	16.00		16.00			1						
FROM EX. I/S		M3-4 M1-4	2.00 2.00	1.00 2.00	2.000 4.000	2.00 4.00			1							
FROM EX. I/S		R2-1	2.50	3.00	7.50	7.50			1							
FROM EX. I/S		W4-2R	3.00	3.00	9.00	9.00			1							
FROM EX. I/S		RIDE SHARE HOT LINE	3.00	3.00	9.00	9.00				1.00						
RAMP E 9+00		W4-1	3.00	3.00	9.00	9.00			1							
RAMP E 6+00 R		R5-1A	3.00	2.00	6.00	6.00			1							
RAMP E 6+00 L		R5-1A	3.00	2.00	6.00	6.00			1							
383+00 R	EB	R5-1 R3-8	3.00 3.00	3.00 2.00	9.00 6.00	9.00 6.00			1							
384+40 L	EB	R4-7	3.00	4.00	12.00		12.00			1						
SUBTOTALS 1					417.37	215.37	58.00	144.00	20.00	4.00	1.00	1.00	3.00	3.00		

EXISTING SIGN REMOVAL																
EXISTING LOCATION	DIRECTION OF TRAVEL	SIGN NUMBER	WIDTH FT	DEPTH FT	SIGN AREA SF	SIGNS						RELOCATE SIGN PANEL ASSEMBLY, EA	REMOVE OVERHEAD STRUCTURE - SPAN, EA	REMOVE GROUND MOUNT SIGN SUPPORT, EA	REMOVE CONCRETE FOUNDATION - GROUND MOUNT, EA	
						REMOVE SIGN PANEL			REMOVE SIGN PANEL ASSEMBLY		TYPE A EA					TYPE B EA
						TYPE 1	TYPE 2	TYPE 3	TYPE A EA	TYPE B EA						
384+50 R	EB	R5-1 R3-8	3.00 2.50	3.00 3.00	9.00 7.50	9.00 7.50				1						
385+00 R	EB	D9-2 ELMHURST M6-3A	2.00 2.00 1.75	2.00 2.00 1.25	4.00 4.00 2.188	4.00 4.00 2.19				1						
385+70 R	WB	M4-5 M1-4 D1-1C M6-3	2.00 2.00 2.00 1.75	1.00 2.00 1.00 1.25	2.000 4.000 2.000 2.188	2.00 4.00 2.00 2.19				1						
386+00R	WB	R5-1	3.00	3.00	9.00	9.00				1						
386+00 L	EB	R5-2 R5-1 D9-2 M6-1LA	3.00 3.00 2.00 1.75	3.00 3.00 2.00 1.25	9.000 9.000 4.000 2.188	9.00 9.00 4.00 2.19				1						
387+00 L	EB	R6-1R	3.00	1.00	3.000	3.00				1						
389+00 R	WB	R5-1a	3.00	2.00	6.00	6.00				1						
389+00 L	WB	R5-1a	3.00	2.00	6.00	6.00				1						
LARCH AVE		R1-1 TO YORK RD	2.50 2.00	2.50 2.00	6.250 4.000	6.25 4.00				1						
RAMP F 4+00 L		R5-1	3.00	3.00	9.00	9.00				1						
RAMP F 4+00 R		R5-1	3.00	3.00	9.00	9.00				1						
SUBTOTALS 2					101.32	101.32	0.00	0.00	11.00	0.00	0.00	0.00	0.00	0.00		
SUBTOTALS 1					417.37	215.37	58.00	144.00	20.00	4.00	1.00	1.00	3.00	3.00		
TOTALS					518.69	316.69	58.00	144.00	31.00	4.00	1.00	1.00	3.00	3.00		

SIGNING QUANTITY SUMMARY		
ITEM	UNIT	TOTAL QNTY.
SIGN PANEL - TYPE 1	SF	406.94
SIGN PANEL - TYPE 2	SF	111.25
SIGN PANEL - TYPE 3	SF	712.00
REMOVE SIGN PANEL ASSEMBLY - TYPE A	EA	31.00
REMOVE SIGN PANEL ASSEMBLY - TYPE B	EA	4.00
REMOVE SIGN PANEL - TYPE 3	SF	144.00
RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EA	1.00
STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	LB	4169.25
METAL POST - TYPE A	FT	405.75
METAL POST - TYPE B	FT	977.5
CONCRETE FOUNDATIONS	CY	14.7
REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EA	1.00
REMOVE GROUND-MOUNTED SIGN SUPPORT	EA	3.00
REMOVE CONCRETE FOUNDATION-GROUND MOUNT	EA	3.00
REINFORCING BARS	LB	1638

FILE NAME = Sign Qty.dgn  
Sign Qty.dgn

USER NAME = 1001engj  
DESIGNED -  
DRAWN - BLV  
CHECKED - SRG  
DATE - 1/18/10  
REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 20 (LAKE STREET)  
SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 173 OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	(4Y&22-3)R-2	DUPAGE	284	173
ILLINOIS FED. AID PROJECT			CONTRACT NO. 62093	