			Signs										Supports & Foundations						
Assembly Number	Proposed Location	Direction of Travel	Sign Number	Width	Depth	Sign Area	Sign Disposition	Clear Height from Ground	Type 1	Type 2	Type 3	Install Reused Sign	Metal Post Type A	Metal Post Type B	Breakaway Supports W6X9	Breakaway Supports W6X15	W Steel	Concrete	Rebar
				FT	FT	SF		FT	Area=9sf	9sf<Area<24sf	Area=24sf		LF	LF	LF	LF	LB	CY	LB
17	377+00		R6-2R	1.50	2.00	3.000	NEW	7	3.00				12.50						
18	LARCH AVE		R1-1	2.50	2.50	6.250	NEW	5	6.25					28.00					
			R3-5R	2.00	2.50	5.000			5.00										
19	376+00 R	WB		8.00	9.50	76.000		7			76.00					38	570	1.4	156.0
19A	376+00 L	WB		8.00	7.50	60.000		7			60.00				33.5		301.5	1.4	156.0
20	374+20 R	WB	R3-I100R	2.00	2.00	4.000	NEW	7	4.00				12.50						
21	371+00 R	WB	R3-8	3.75	2.00	7.500		7	7.50					26.00					
21	371+00 L	WB	R3-8	3.75	2.00	7.500		7	7.50					26.00					
22	369+00 M	WB		12.00	6.50	78.000		7			78.00				31.5		283.5	1.4	156.0
23	369+00 R	WB		12.50	6.50	81.250		7			81.25					33	495	1.4	156.0
23	RAMP F	WB		12.50	6.50	81.250		7			81.25					33	495	1.4	156.0
24	366+00 R	WB	M3-4	2.00	1.00	2.000	NEW	7	2.00					14.00					
			M1-4	2.00	2.00	4.000			4.00										
24	356+00 R	WB	M3-4	2.00	1.00	2.000	NEW	7	2.00					14.00					
			M1-4	2.00	2.00	4.000			4.00										
25	360+00 R	WB	W4-3	3.00	3.00	9.000	NEW	7	9.00				25.00						
25	RAMP F 7+40 L		W4-3	3.00	3.00	9.000	NEW	7	9.00				25.00						
26	RAMP E 11+00 L		W4-2R	3.00	3.00	9.000	NEW	7	9.00				25.00						
26	RAMP E 11+00 R		W4-2R	3.00	3.00	9.000	NEW	7	9.00				25.00						
27	RAMP F 3+00 L		R5-I100	4.00	5.50	22.000	NEW	7		22.00					29.5		265.5	1.4	156.0
27	RAMP F 3+00 R		R5-I100	4.00	5.50	22.000	NEW	7		22.00					29.5		265.5	1.4	156.0
28	RAMP F 5+00 R		M3-2A	2.50	1.25	3.125	NEW	7	3.13					61.00					
			M1-1	3.75	3.00	11.250				11.25									
			M3-2	2.50	1.25	3.125	NEW	7	3.13										
			M1-4	3.00	3.00	9.000			9.00										
29	386+20 L	EB	R6-1R	3.00	1.00	3.000	NEW	7	3.00					12.00					
30	385+00 R	EB	D9-2	2.00	2.00	4.000	NEW	7	4.00					33.00					
				2.00	2.00	4.000			4.00										
			M6-3A	1.75	1.25	2.188			2.19										
31	388+50 R	WB	R5-1A	3.00	2.00	6.000	NEW	7	6.00					13.00					
31	388+50 L	WB	R5-1A	3.00	2.00	6.000	NEW	7	6.00					13.00					
31	RAMP E 5+00 L		R5-1A	3.00	2.00	6.000	NEW	7	6.00					13.00					
31	RAMP E 5+00 R		R5-1A	3.00	2.00	6.000	NEW	7	6.00					13.00					
32	384+50 R	EB	R5-1	3.00	3.00	9.000	NEW	7	9.00				27.00						
32	385+50 R	WB	R5-1	3.00	3.00	9.000	NEW	7	9.00				27.00						
32	387+00 R	WB	R5-1	3.00	3.00	9.000	NEW	7	9.00				27.00						
32	387+00 L	WB	R5-1	3.00	3.00	9.000	NEW	7	9.00				27.00						
32	RAMP E 4+00 L		R5-1	3.00	3.00	9.000	NEW	7	9.00				27.00						
32	RAMP E 4+00 R		R5-1	3.00	3.00	9.000	NEW	7	9.00				27.00						
33	386+00 L	WB	D9-2	2.00	2.00	4.000	NEW	7	4.00				12.75						
			M6-1LA	1.75	1.25	2.188	NEW		2.19										
34	RAMP F 4+00 R		Ride Share Hot Line			12.000		7				1		30.00					
35	388+50 R	WB	R3-8k	4	2.5	10.000	NEW	7		10.00				27.00					
35	388+50 L	WB	R3-8k	4	2.5	10.000	NEW	7		10.00				27.00					
36	Larch Ave		R1-1	2.5	2.5	6.250	NEW	7	6.25					13.50					
36	Frontage Rd.		R1-1	2.5	2.5	6.250	NEW	7	6.25					13.50					
37	386+50 R	WB	M4-5	2.00	1.00	2.000	NEW	5	2.00					33.00					
			M1-4	2.00	2.00	4.000	NEW		4.00										
			D1-1C	2.00	1.00	2.000	NEW		2.00										
			M6-3	1.75	1.25	2.188	NEW		2.19										
								Total	406.94	111.25	712.00	1.00	405.75	977.50	168.25	177.00	4169.3	14.7	1638.0

FILE NAME = Sign Qty.dgn	USER NAME = IDOT(eng)	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	U.S. ROUTE 20 (LAKE STREET) SCHEDULE OF QUANTITIES
Sign Qty.dgn		DRAWN - BLV	REVISED -		
	PLOT SCALE = 1"=50'	CHECKED - SRG	REVISED -		
	PLOT DATE = 1/13/2010	DATE - 1/18/10	REVISED -		SCALE: N.T.S. SHEET NO. 175 OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	(4Y&22-3)R-2	DUPAGE	284	175
		CONTRACT NO. 62093		
		ILLINOIS FED. AID PROJECT		