

SUMMARY OF QUANTITIES				100% STATE															
CODE	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY FAP 365	ROADWAY NAPERVILLE RD HERRICK RD	ROADWAY CROSS RDS.	IL 56	IL 56	IL 56	IL 56	IL 56	IL 56	IL 56	IL 56	IL 56	IL 56	IL 56	IL 56	IL 56
				IL 56	DUPAGE CO.	WHEATON	CULVERTS	IL 56	NAPERVILLE RD	TRAF. SIG. HERRICK-WIES. RD	TRAF. SIG. ORCHARD RD	TRAF. SIG. CROMWELL DR	IL 56 WATERMAIN RELOCATION	TRAF. SIGNALS NAPERVILLE RD	TRAF. SIGNALS DANADA SQ.	SIGNING	LANDSCAPING		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	350	250	50	50													
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	200	100	50	50													
20101000	TEMPORARY FENCE	FOOT	8,950	6,291	2,117	542													
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	75	75															
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	75	75															
20200100	EARTH EXCAVATION	CU YD	103,346	80,782	19,781	2,783													
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	70,551	63,264	5,538	90	1,651												
20400800	FURNISHED EXCAVATION	CU YD	21,098	21,098															
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1,999				1,999												
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	4,849	1,091	2,107		1,651												
20800150	TRENCH BACKFILL	CU YD	9,350	2,856	1,601	15		954						3,924					
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	34,511	19,911	14,600														
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	77,982																77,982
* 21101630	TOPSOIL FURNISH AND PLACE, 8"	SQ YD	45,153																45,153
* 21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	12,993																12,993
* 21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	27,399																27,399
* 21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	11,051																11,051
* 25000210	SEEDING, CLASS 2A	ACRE	16																16
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,438																1,438
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,438																1,438
* 25000750	MOWING	ACRE	20																20
* X2502014	SEEDING, CLASS 4A (MODIFIED)	ACRE	18																18
* X2502024	SEEDING, CLASS 4B (MODIFIED)	ACRE	3																3
* 25100115	MULCH, METHOD 2	ACRE	22	20	2														
* 25100630	EROSION CONTROL BLANKET	SQ YD	181,257																181,257
* 25100900	TURF REINFORCEMENT MAT	SQ YD	725																725
* 25200110	SODDING, SALT TOLERANT	SQ YD	12,166																12,166
* 25200200	SUPPLEMENTAL WATERING	UNIT	50																50
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	1,440	1,440															
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,165	2,023	142														
28000305	TEMPORARY DITCH CHECKS	FOOT	2,832	2,832															
28000400	PERIMETER EROSION BARRIER	FOOT	39,760	30,483	5,898	3,379													
28000500	INLET AND PIPE PROTECTION	EACH	45	40	2	3													
28000510	INLET FILTERS	EACH	96	39	57														
28100105	STONE RIPRAP, CLASS A3	SQ YD	53	53															