

SUMMARY OF QUANTITIES				100% STATE						90% STATE 5% WHEATON 5% DUPAGE	93.3% STATE 6.7% WHEATON	93.3% STATE 6.7% WHEATON	100% WHEATON (50% WHEATON 50% WARRENVILLE FOR HERRICK ONLY)	90% STATE 10% DUPAGE	80% STATE 20% DUPAGE	100% STATE	
				ROADWAY FAP 365	ROADWAY NAPERVILLE RD HERRICK RD	ROADWAY CROSS RDS.	IL 56	TRAFFIC SIGNAL INTERCONNECT		IL 56 BUTTERFIELD RD	NAPERVILLE RD	TRAF. SIG. HERRICK-WIES. RD	TRAF. SIG. ONCHARD RD	TRAF. SIG. CROMWELL DR	EMERGENCY VEHICLE PRE-EMPTION	TRAFFIC SIGNALS NAPERVILLE RD	TRAFFIC SIGNALS DANADA SQ.
CODE	DESCRIPTION	UNIT	TOTAL QUANTITY	0003	0003	0004	0040	0021	0021	0021	0021	0021	0021	0021	0021	0021	
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	3							1	1	1					
87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1							1							
87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1								1						
87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1								1						
87700400	STEEL MAST ARM ASSEMBLY AND POLE, 60 FT.	EACH	1										1				
87700414	STEEL MAST ARM ASSEMBLY AND POLE, 66 FT.	EACH	1										1				
87702518	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 34 FT. AND 16 FT.	EACH	1									1					
87702574	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 36 FT. AND 54 FT.	EACH	1														
87702600	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 38 FT. AND 44 FT.	EACH	1												1		
87702662	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 42 FT. AND 60 FT.	EACH	1							1							
87702245	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 20 FT. AND 55 FT.	EACH	1										1				
87702990	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT.	EACH	1												1		
87703050	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 64 FT.	EACH	1												1		
87703224	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 48 FT. AND 24 FT.	EACH	1										1				
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	44							12	4	4	24				
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	20							4	4	4	4	4			
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	40							10		10	10	10			
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	211							39	55	36	41	40			
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	88							21			46	21			
87900200	DRILL EXISTING HANDHOLE	EACH	2					2									
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	33							3	4	7	13	6			
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2									2					
88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2								2						
88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	4								4						
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	6							1			3	2			
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	31							11	3	2	9	6			
88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1							1							
88030230	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	1								1						
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1										1				
88030250	SIGNAL HEAD, LED, 2-FACE, 1-4 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1								1						
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	13							4	2	2	3	2			
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	7							2			2	3			
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	64							14	7	9	22	12			
88500100	INDUCTIVE LOOP DETECTOR	EACH	61							13	11	8	23	6			
88600100	DETECTOR LOOP, TYPE I	FOOT	4,323							1,234	1,026	699	1,143	221			
88700200	LIGHT DETECTOR	EACH	11										11				

* SPECIALTY ITEMS
 ** NON-PARTICIPATING ITEM

FILE NAME =	DESIGNED - JMM	REVISED -
...General\DI62419-aoc--008.dgn	DRAWN - TMB	REVISED -
USER NAME = BENESCH	CHECKED - RMT	REVISED -
PLOT DATE = 12/3/2010	DATE - 12/6/10	REVISED -

benesch

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 8 OF 12 SHEETS STA. TO STA.

F.A.P. RTE. 365	SECTION (57 & 58)WRS-2	COUNTY DUPAGE	TOTAL SHEETS 681	SHEET NO. 12
ILLINOIS FED. AID PROJECT			CONTRACT NO. 62419	

Rev 1-7-11