

20101000

TEMPORARY FENCE

LOCATION	STATION	OFFSET		UNIT
		LEFT FEET	RIGHT FEET	
ORCHARD RD	908+36		32	
ORCHARD RD	908+44		32	
ORCHARD RD	908+50		31	
ORCHARD RD	908+63		32	
ORCHARD RD	908+78		28	
ORCHARD RD	908+96		22	
ORCHARD RD	907+87	35		79
ORCHARD RD	907+54	42		
NAPERVILLE RD	11010+60		40	47
NAPERVILLE RD	11010+98		41	58
NAPERVILLE RD	11011+10		41	
NAPERVILLE RD	11011+05	48		70
NAPERVILLE RD	11011+10		41	
NAPERVILLE RD	11011+30	47		
NAPERVILLE RD	11012+20	48		290
NAPERVILLE RD	11012+22	62		
NAPERVILLE RD	11012+28	50		
NAPERVILLE RD	11012+39	51		
NAPERVILLE RD	11012+61	47		
NAPERVILLE RD	11012+92	49		
NAPERVILLE RD	11013+01	48		
NAPERVILLE RD	11013+32	51		
NAPERVILLE RD	11013+44	50		
NAPERVILLE RD	11013+72	49		
NAPERVILLE RD	11013+86	49		
NAPERVILLE RD	11014+22	52		
NAPERVILLE RD	11014+53	53		
NAPERVILLE RD	11014+57	52		
NAPERVILLE RD	11026+13		81	333
NAPERVILLE RD	11026+22		68	
NAPERVILLE RD	11026+60		76	
NAPERVILLE RD	11027+11		74	
NAPERVILLE RD	11027+59		69	
NAPERVILLE RD	11027+85		67	
NAPERVILLE RD	11028+52		71	
NAPERVILLE RD	11028+95		69	
NAPERVILLE RD	11026+55	68		188
NAPERVILLE RD	11027+14	69		
NAPERVILLE RD	11027+57	67		
NAPERVILLE RD	11027+97	68		
NAPERVILLE RD	11030+49	67		85
NAPERVILLE RD	11030+88	65		
NAPERVILLE RD	11030+88		74	47
NAPERVILLE RD	11033+69	64		49
NAPERVILLE RD	11033+70	65		
NAPERVILLE RD	11034+49	76		47
NAPERVILLE RD	11034+99	84		47
NAPERVILLE RD	11036+21	83		47
NAPERVILLE RD	11036+08		64	164
NAPERVILLE RD	11036+33		61	
NAPERVILLE RD	11036+61		60	
NAPERVILLE RD	11036+84		65	
NAPERVILLE RD	11037+03		63	
NAPERVILLE RD	11037+23		66	
NAPERVILLE RD	11037+03	58		185
NAPERVILLE RD	11037+13	62		
NAPERVILLE RD	11037+78	66		
NAPERVILLE RD	11038+20	64		
NAPERVILLE RD	11038+35	65		
NAPERVILLE RD	11038+42	50		
NAPERVILLE RD	11037+90		60	47
TOTAL				8950

DRIVEWAY SCHEDULE

LOCATION	ROAD	STATION	SIDE	35101500	35501308	35501316	40603310
				AGGREGATE BASE COURSE, TYPE B	HOT-MIX ASPHALT BASE COURSE, 6"	HOT-MIX ASPHALT BASE COURSE, 8"	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50
				(SQ YD)	(SQ YD)	(SQ YD)	(TON)
IL-56	261+29.85	LT		113	-	-	13
IL-56	264+87.53	LT		147	-	-	16
IL-56	264+69.59	RT			62	7	7
IL-56	265+15.14	RT			95	11	11
IL-56	288+46.47	LT			136	15	15
IL-56	399+68.55	RT		40			
Herrick	809+30.00	RT			54	-	6
Orchard	903+18.00	RT			59	-	7
Orchard	907+57.00	LT			77	-	9
Naperville	11018+17.08	LT				62	7
				40	450	355	91

SURVEY MARKER SCHEDULE

LOCATION			66700095 PERMANENT SURVEY MARKERS (EACH)
ROAD	STATION	LOCATION	
IL56	239+23.56	PC C4	1.0
IL56	263+33.07	PT C4	1.0
IL56	273+38.43	PC C5	1.0
IL56/HERRICK	284+84.39	POT	1.0
IL56	301+72.48	PT C5	1.0
IL56	343+60.03	PC C6	1.0
IL56/ORCHARD	344+29.77	POT	1.0
IL56	357+68.91	PT C6	1.0
IL56/CROMWELL	370+61.40	POT	1.0
IL56	400+48.08	POT	1.0
IL56/NAPERVILLE	400+52.69	POT	1.0
IL56	410+16.56	PC C8	1.0
IL56	426+48.89	PT C8	1.0
HERRICK	805+83.93	POT	1.0
HERRICK	810+35.27	PC C1	1.0
HERRICK	814+59.93	POT	1.0
HERRICK	816+48.89	PT C1	1.0
HERRICK	821+59.79	PC C2	1.0
ORCHARD/IL56	900+00.00	POT	1.0
ORCHARD	902+58.38	POT	1.0
ORCHARD	904+53.34	POT	1.0
ORCHARD	906+53.35	POT	1.0
ORCHARD	909+22.30	POT	1.0
ORCHARD	910+12.98	POT	1.0
CROMWELL	10000+00.00	POT	1.0
CROMWELL	10003+54.95	POT	1.0
NAPERVILLE	11008+11.65		1.0
NAPERVILLE	11012+04.31	POT	1.0
NAPERVILLE	11024+04.41	POT	1.0
NAPERVILLE/IL56	11024+06.82	POT	1.0
NAPERVILLE	11032+03.69	POT	1.0
NAPERVILLE	11048+68.75	POT	1.0

PAVEMENT SCHEDULE

LOCATION	40701941		40603148		40603153		40603595		40600200		40600300		Z0001050		Z0001056		42400200		XX008001		40600625		35600720		44201769	
	ROAD	Station From	Station To	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13"	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90, 10"	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	AGGREGATE SUBGRADE 12"	AGGREGATE SUBGRADE 16"	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	AGGREGATE PATH, 8"	LEVELING BINDER (MACHINE METHOD), N50	HOT-MIX ASPHALT BASE COURSE WIDENING, 11"	CLASS D PATCHES, TYPE III, 10 INCH									
IL56	255+00.00	258+00.00	-	179	1,600	1,600	179	1	3	2,609	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
IL56	258+00.00	273+00.00	-	1,018	1,018	9093	7	18	13,556	-	-	-	-	58	-	-	-	-	-	-	-	-	-	-	-	-
IL56	273+00.00	288+00.00	-	1,421	1,421	12690	10	25	16,714	-	-	1,008	1,607	-	-	-	-	-	-	-	-	-	-	-	-	-
IL56	288+00.00	303+00.00	-	1,225	1,225	10935	9	22	16,220	-	-	4,722	-	-	-	-	-	-	-	-	-	-	-	-	-	-
IL56	303+00.00	318+00.00	-	1,051	1,051	9384	8	19	15,943	-	-	7,413	-	-	-	-	-	-	-	-	-	-	-	-	-	-
IL56	318+00.00	333+00.00	-	1,396	1,396	12463	10	25	16,462	-	-	5,797	-	-	-	-	-	-	-	-	-	-	-	-	-	-
IL56	333+00.00	348+00.00	-	1,249	1,249	11150	9	22	15,189	-	-	8,333	-	-	-	-	-	-	-	-	-	-	-	-	-	-
IL56	348+00.00	363+00.00	-	908	908	8107	6	16	12,777	-	-	7,443	-	-	-	-	-	-	-	-	-	-	-	-	-	-
IL56	363+00.00	378+00.00	-	1,257	1,257	11221	9	22	15,154	-	-	4,499	-	-	-	-	-	-	-	-	-	-	-	-	-	-
IL56	378+00.00	393+00.00	-	1,506	1,506	13448	11	27	17,267	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
IL56	393+00.00	408+00.00	-	2,520	2,520	22504	18	45	2,910	-	-	5,422	-	-	-	-	-	-	-	-	-	-	-	-	-	-
IL56	408+00.00	417+54.70	-	1,112	1,112	9928	7	18	12,185	-	-	4,164	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cromwell	10001+59.30	10001+73.43	-	7	7	66	1	2	82	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Herrick	806+65.00	813+47.00	3,054	-	-	-	2	6	-	4,183	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Wiesbrook	815+71.00	819+71.00	-	-	-	-	1	3	265	-	-	318	-	-	176	-	-	-	-	-	-	-	-	145	21	-
Orchard	901+05.00	909+43.00	-	361	361	3,226	3	6	4,202	-	-	1,001	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Naperville	11010+75.62	11015+44.00	2,415	-	-	-	2	5	-	3,085	4,129	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Naperville	11015+44.00	11019+00.00	2,537	-	-	-	2	5	-	3,085	3,645	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Naperville	11019+00.00	11021+75.45	2,791	-	-	-	2	6	-	3,394	3,461	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Naperville	11026+12.34	11031+46.74	6,056	-	-	-	5	12	-	7,235	3,978	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Naperville	11031+46.74	11034+00.00	3,171	-	-	-	3	6	-	3,635	1,580	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Naperville	11034+00.00	11038+47.53	4,473	-	-	-	3	9	-	5,408	1,907	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
WESBROOK TO LAKE VIEW - WM CONSTR																	4100	-	-	-	-	-	171			
TOTAL			24,497	15,211	15,211	135,815	178	129	324	161,533	30,025	72,919	1,607	234	145	192										

FILE NAME = ... \General\10162419-sch--003.dgn
USER NAME = tbi1ank
PLOT DATE = 1/10/2011

DESIGNED - JMM
DRAWN - TMB
CHECKED - RMT
DATE - 12/6/10

REVISED ADDENDUM A -1/10/11
REVISED -
REVISED -
REVISED -

benesch

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 2 OF 11 SHEETS STA. TO STA.

F.A.P. RTE. 365 SECTION (57 & 58)WRS-2 COUNTY DUPAGE TOTAL SHEETS 681 SHEET NO. 29 CONTRACT NO. 62419 ILLINOIS FED. AID PROJECT