

SUMMARY OF QUANTITIES				100% STATE					90% STATE 5% WHEATON 5% DUPAGE	93.3% STATE 6.7% WHEATON	93.3% STATE 6.7% WHEATON	100% WHEATON (50% WHEATON 50% WARRENVILLE FOR HERRICK ONLY)	90% STATE 10% DUPAGE	80% STATE 20% DUPAGE	100% STATE	
				ROADWAY FAP 365	ROADWAY NAPERVILLE RD HERRICK RD	ROADWAY CROSS RDS.	IL 56	TRAFFIC SIGNAL INTERCONNECT		TRAFF. SIG. HERRICK-WIES. RD	TRAFF. SIG. ORCHARD RD	TRAFF. SIG. CROWNELL DR	EMERGENCY VEHICLE PRE-EMPTION	TRAFFIC SIGNALS NAPERVILLE RD	TRAFFIC SIGNALS DANADA SQ.	SIGNING
CODE	DESCRIPTION	UNIT	TOTAL QUANTITY	IL 56	DUPAGE CO.	WHEATON	CULVERTS	IL 56 BUTTERFIELD RD	NAPERVILLE RD						0021	0031
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	100	100												
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	14,825					11,377		620	610	551		1,201	466	
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	313							36	10	94		173		
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	321							140	14	36		76	55	
* 81000900	CONDUIT IN TRENCH, 3 1/2" DIA., GALVANIZED STEEL	FOOT	27												27	
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	237							20	20	157		20	20	
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	2,590					1,357		254	235	123		406	215	
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	2,805							560	438	260		1,142	405	
* 81400100	HANDHOLE	EACH	24					12		1		1		5	5	
* 81400200	HEAVY-DUTY HANDHOLE	EACH	53					28		7	8	4		6		
* 81400300	DOUBLE HANDHOLE	EACH	9							2	1	1		4	1	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	15,676					11,377		638	741	911		1,489	520	
* 82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	2												2	
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1					1								
* 85700205	FULL ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	5							1	1	1		1	1	
* 86000105	MASTER CONTROLLER (SPECIAL)	EACH	1					1								
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	5							1	1	1		1	1	
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	6,738							2,285	187	229		2,467	1,570	
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	8,062							2,083	200	565		3,099	2,115	
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	10,256							997	1,067	1,958		5,021	1,213	
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	10,318							3,636	2,385	571		2,286	1,440	
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	20,681							4,069	2,740	2,485		10,583	804	
* 87301615	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 16 6 PAIR	FOOT	843												843	
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	504							130	80	65		79	150	
* 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	4							1				3		
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	1									1				
* 87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	1								1					
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	5							2				3		
* 87601100	PEDESTRIAN PUSH-BUTTON POST, GALVANIZED STEEL, TYPE I	EACH	1							1						
* 87700120	STEEL MAST ARM ASSEMBLY AND POLE, 16 FT.	EACH	1												1	
* 87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1									1				
* 87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1											1		
* 87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1							1						
* 87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	2								1			1		
* 87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	2									1		1		

\* SPECIALTY ITEMS  
 \*\* NON-PARTICIPATING ITEM

FILE NAME =	DESIGNED - JMM	REVISED -	<b>benesch</b>	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...General\0162419-soq--887.dgn	DRAWN - TMB	REVISED -			365	(57 & 58)WRS-2	DUPAGE	681	11			
USER NAME = BENESCH	CHECKED - RMT	REVISED -			SCALE: N.T.S. SHEET NO. 7 OF 12 SHEETS STA. TO STA.			CONTRACT NO. 62419				
PLOT DATE = 12/3/2010	DATE - 12/6/10	REVISED -			ILLINOIS FED. AID PROJECT							