

SUMMARY OF QUANTITIES				100% STATE					90% STATE	93.3% STATE	93.3% STATE	100% WHEATON	90% STATE	80% STATE	100% STATE		
				ROADWAY FAP 365	ROADWAY NAPERVILLE RD HERRICK RD	ROADWAY CROSS RDS.	IL 56	TRAFFIC SIGNAL INTERCONNECT		5% WHEATON 5% DUPAGE	6.7% WHEATON	6.7% WHEATON	50% WHEATON 50% WARRENVILLE FOR HERRICK ONLY	10% DUPAGE	20% DUPAGE	SIGNING	LANDSCAPING
				IL 56	DUPAGE CO.	WHEATON	CULVERTS	IL 56 BUTTERFIELD RD	NAPERVILLE RD	TRAF. SIG. HERRICK-WIES. RD	TRAF. SIG. ORCHARD RD	TRAF. SIG. CROWWELL DR	EMERGENCY VEHICLE PRE-EMPTION	TRAFFIC SIGNALS NAPERVILLE RD	TRAFFIC SIGNALS DAMADA SQ.	0021	0031
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	4														
87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1														
87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1														
87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1														
87700400	STEEL MAST ARM ASSEMBLY AND POLE, 60 FT.	EACH	1														
87700414	STEEL MAST ARM ASSEMBLY AND POLE, 66 FT.	EACH	1														
87702518	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 34 FT. AND 16 FT.	EACH	1														
87702574	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 36 FT. AND 54 FT.	EACH	1														
87702600	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 38 FT. AND 44 FT.	EACH	1														
87702662	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 42 FT. AND 60 FT.	EACH	1														
87702245	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 20 FT. AND 55 FT.	EACH	1														
87702990	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT.	EACH	1														
87703050	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 64 FT.	EACH	1														
87703224	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 48 FT. AND 24 FT.	EACH	1														
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	44														
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	20														
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	40														
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	211														
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	88														
87900200	DRILL EXISTING HANDHOLE	EACH	2														
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	33														
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2														
88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2														
88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	4														
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	6														
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	31														
88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1														
88030230	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	1														
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1														
88030250	SIGNAL HEAD, LED, 2-FACE, 1-4 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1														
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	13														
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	7														
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	64														
88500100	INDUCTIVE LOOP DETECTOR	EACH	61														
88600100	DETECTOR LOOP, TYPE I	FOOT	4,323														
88700200	LIGHT DETECTOR	EACH	11														

* SPECIALTY ITEMS
 ** NON-PARTICIPATING ITEM

FILE NAME =	DESIGNED - JMM	REVISED -
...General\0162419-soq-008.dgn	DRAWN - TMB	REVISED -
USER NAME = BENESCH	CHECKED - RMT	REVISED -
PLOT DATE = 12/3/2010	DATE - 12/6/10	REVISED -

benesch

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 8 OF 12 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(57 & 58)WRS-2	DUPAGE	681	12
ILLINOIS FED. AID PROJECT				
CONTRACT NO. 62419				