

SIGNING SCHEDULE

LOCATION		DESCRIPTION		72000100	72000200	72900300	73000100	72800100	73100100
ROADWAY	STATION	SIGN LEGEND SYMBOL	CODE	SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	METAL POSTS TYPE A	WOOD SIGN SUPPORT	TELESCOPING STEEL SIGN SUPPORT	BASE FOR TELESCOPING STEEL SIGN SUPPORT
				AREA (SQ FT)	AREA (SQ FT)	FOOT	FOOT	FOOT	EACH
IL RTE 56	325+80.00	ONE WAY RT	R6-2R	3.00				12	1
IL RTE 56	328+71.00	LEFT ONLY	R3-5L	5.00				17	1
IL RTE 56	328+71.00	KEEP RT	R4-7	5.00				-	-
IL RTE 56	328+76.00	STOP	R1-1	6.25		13		-	-
IL RTE 56	329+74.00	KEEP RT	R4-7	5.00				12.5	1
IL RTE 56	338+75.00	SPD LMT 45	R2-1	7.50		13.5			
IL RTE 56	338+75.00	SPD LMT 45	R2-1	7.50		13.5			
IL RTE 56	340+31.10	LT TN ONLY	R3-5L	5.00				12.5	1
IL RTE 56	341+75.00	ADOPT A HIGHWAY	-	5.00		13.25			
IL RTE 56	341+75.00	ST DANIEL'S KOC	-	1.88					
IL RTE 56	343+60.00	LT TN ONLY	R3-5L	5.00				15	1
IL RTE 56	343+60.00	KEEP RT	R4-7	5.00				-	-
IL RTE 56	345+00.00	RT TN ONLY	R3-5	5.00		13			
IL RTE 56	345+25.00	LT TN ONLY	R3-5L	5.00				17	1
IL RTE 56	345+25.00	KEEP RT	R4-7	5.00				-	-
IL RTE 56	346+10.00	NO PKG ALONG HWY	R8-1 MOD	5.00		12			
IL RTE 56	347+10.00	RT TN ONLY	R3-5R	5.00		13			
IL RTE 56	349+00.00	EAST	M3-2	2.00		13.5			
IL RTE 56	349+00.00	ILLINOIS 56	M1-5	4.00		-			
IL RTE 56	349+50.00	WEST	M3-2	2.00		13.5			
IL RTE 56	349+50.00	ILLINOIS 56	M1-5	4.00		-			
IL RTE 56	353+50.00	SPD LMT 45	R2-1	7.50		13.5			
IL RTE 56	353+50.00	SPD LMT 45	R2-1	7.50		13.5			
IL RTE 56	365+55.00	LT TN ONLY	R3-5L	5.00				14.5	1
IL RTE 56	366+50.00	SPD LMT 45	R2-1	7.50		13.5			
IL RTE 56	366+50.00	SPD LMT 45	R2-1	7.50		13.5			
IL RTE 56	370+00.00	RT TN ONLY	R3-5R	5.00				17	1
IL RTE 56	370+00.00	KEEP RT	R4-7	5.00				-	-
IL RTE 56	371+15.00	KEEP RT	R4-7	5.00				14.5	1
IL RTE 56	371+40.00	RT TN ONLY	R3-5R	5.00		13			
IL RTE 56	374+06.00	RT TN ONLY	R3-5R	5.00		13			
IL RTE 56	375+00.00	WEST	M3-2	2.00		13.5			
IL RTE 56	375+00.00	RTE MKR	M1-5	4.00		-			
IL RTE 56	376+00.00	EAST	M3-2	2.00		13.5			
IL RTE 56	376+00.00	RTE MKR	M1-5	4.00		-			
IL RTE 56	383+00.00	SPD LMT 45	R2-1	7.50		13.5			
IL RTE 56	383+00.00	SPD LMT 45	R2-1	7.50		13.5			
IL RTE 56	383+70.00	LT TN ONLY	R3-5L	5.00				14.5	1
IL RTE 56	385+80.00	NO PKG ALONG HWY	R8-1 MOD	5.00		12			
IL RTE 56	387+55.00	NO PKG ALONG HWY	R8-1 MOD	5.00		12			
IL RTE 56	387+66.00	STOP	R1-1	6.25		13			
IL RTE 56	387+67.00	LT TN ONLY	R3-5L	5.00				12.5	1
IL RTE 56	387+67.00	KEEP RT	R4-7	5.00				-	-
IL RTE 56	387+85.00	NO PARKING SYM	R8-3a	4.00		12.5			
IL RTE 56	388+55.00	BUTTERFIELD RD	-	1.88		11.5			
IL RTE 56	388+55.00	WEST LOOP RD	-	1.88		-			
IL RTE 56	388+68.00	KEEP RT	R4-7	5.00				15.5	1
IL RTE 56	388+68.00	LT TN ONLY	R3-5L	5.00				-	-
IL RTE 56	389+00.00	NO PKG ALONG HWY	R8-1 MOD	5.00		12			
IL RTE 56	390+82.00	RT TN ONLY	R3-5R	5.00		13			
IL RTE 56	390+95.00	STOP	R1-1	6.25		13			
IL RTE 56	391+00.00	NO PKG ALONG HWY	R8-1 MOD	5.00		12			
IL RTE 56	391+60.00	RIGHT ONLY	R3-5L	5.00		13			
IL RTE 56	392+30.00	LT TN ONLY	R3-5L	5.00				12.5	1
IL RTE 56	392+85.00	MERGE RT		6.25		14			
IL RTE 56	393+30.00	STOP	R1-1	6.25		13			
IL RTE 56	393+60.00	NO PKG ANY TIME	R7-1	1.50		12			
IL RTE 56	395+25.00	RIGHT ONLY	R3-5R	5.00		13.5			
IL RTE 56	397+15.00	SPD LMT 45	R2-1	7.50		13.5			
IL RTE 56	397+80.00	ADOPT A HIGHWAY	5	5.00		13.25			
IL RTE 56	397+80.00	TAE KWON - DO	1.88	1.88		-			
IL RTE 56	398+00.00	RT TN ONLY	R3-5R	5.00		13			
IL RTE 56	398+15.00	BRIDGE	2			15.5			
IL RTE 56	398+15.00	WEIGHT LIMIT 15 T	5			-			
IL RTE 56	398+15.00	3 MILES AHEAD	3			-			
IL RTE 56	398+88.00	RT LN ENDS		9.00		14.75			
IL RTE 56	399+22.00	KEEP RT	R4-7	5.00				16	1
IL RTE 56	399+22.00	LT TN ONLY	R3-8 MOD	9.00				-	-

SIGNING SCHEDULE

LOCATION		DESCRIPTION		72000100	72000200	72900300	73000100	72800100	73100100
ROADWAY	STATION	SIGN LEGEND SYMBOL	CODE	SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	METAL POSTS TYPE A	WOOD SIGN SUPPORT	TELESCOPING STEEL SIGN SUPPORT	BASE FOR TELESCOPING STEEL SIGN SUPPORT
				AREA (SQ FT)	AREA (SQ FT)	FOOT	FOOT	FOOT	EACH
IL RTE 56	399+25.00	WEST	M3-2	2.00		13.5			
IL RTE 56	399+25.00	ILLINOIS 56	M1-5	4.00		-			
IL RTE 56	401+75.00	KEEP RT	R4-7	5.00				16	1
IL RTE 56	401+75.00	LT TN ONLY	R3-8 MOD	9.00				-	-
IL RTE 56	402+40.00	RT TN ONLY	R3-5R	5.00		13			
IL RTE 56	402+82.00	EAST	M3-2	2.00		13.5			
IL RTE 56	402+82.00	ILLINOIS 56	M1-5	4.00		-			
IL RTE 56	403+68.00	BUS STOP	R4-7			13			
IL RTE 56	404+30.00	SPD LMT 45	R2-1	7.50		13.5			
IL RTE 56	405+00.00	ADOPT A HIGHWAY		5.00		13.25			
IL RTE 56	405+00.00	TAE KWON - DO		1.88		-			
IL RTE 56	406+00.00	NO PRK ANY TIME	R7-1	1.50		12			
IL RTE 56	406+00.00	NO PRK ANY TIME	R7-1	1.50		12			
IL RTE 56	408+40.00	STOP	R1-1	6.25		13			
IL RTE 56	410+44.00	KEEP RT	R4-7	5.00		15			
IL RTE 56	410+44.00	LT TN ONLY	R3-5L	5.00		-			
IL RTE 56	410+62.00	STOP	R1-1	6.25		13			
IL RTE 56	411+50.00	KEEP RT	R4-7	5.00		15			
IL RTE 56	411+50.00	LT TN ONLY	R3-5L	5.00		-			
IL RTE 56	414+75.00	SPD LMT 45	R2-1	7.50		13.5			
IL RTE 56	414+75.00	SPD LMT 45	R2-1	7.50		13.5			
IL RTE 56	416+32.00	BUS STOP	R4-7			13			
HERRICK	810+75.00	LT, THRU, RT ONLY	R3-8b		10		14.5		
HERRICK	813+00.00	ILLINOIS 56	M1-5	4		13.5			
HERRICK	813+00.00	DIRECTIONAL ARROW	M6-4	2					
HERRICK	813+00.00	SPD LMT 45	R2-1	7.5		13.5			
HERRICK	813+75.00	LT, THRU, RT ONLY	R3-8b		10		14.5		
HERRICK	815+32.00	ILLINOIS 56	M1-5	4		13.5			
HERRICK	815+32.00	DIRECTIONAL ARROW	M6-4	2					
ORCHARD	900+92.00	LT, THRU/LT, RT ONLY	R3-8a		10		14.5		
ORCHARD	902+00.00	SPD LMT 30	R2-1	7.5		13.5			
ORCHARD	905+35.00	LT, THRU/LT, RT ONLY	R3-8a		10		14.5		
CROMWELL	10000+78.00	STOP	R1-1	6.25		13			
NAPERVILLE	11017+60.00	RT TN ONLY	R3-5R	5		13			
NAPERVILLE	11019+15.00	DEER XING	W1-3	6.25		14			
NAPERVILLE	11019+20.00	DUAL RT ONLY	R3-8R MOD		10		15.5		
NAPERVILLE	11019+40.00	DUAL LT ONLY	R3-8L MOD		10		15.5		
NAPERVILLE	11020+20.00	BUS STOP	R4-7			13			
NAPERVILLE	11021+25.00	SPD LMT 50	R2-1			13.5			
NAPERVILLE	11022+98.00	DUAL LT ONLY	R3-8L MOD		10		18		
NAPERVILLE	11022+98.00	KEEP RT	R4-7	5		-			
NAPERVILLE	11025+25.00	DUAL LT ONLY	R3-8L MOD		10		18		
NAPERVILLE	11025+25.00	KEEP RT	R4-7	5		-			
NAPERVILLE	11027+00.00	RT TN ONLY	R3-5R	5		13			
NAPERVILLE	11028+00.00	RT TN ONLY	R3-5R	5		13			
NAPERVILLE	11028+20.00	SPD LMT 40	R2-1	7.5		13.5			
NAPERVILLE	11028+45.00	RT TN ONLY	R3-5R	5		15.5			
NAPERVILLE	11028+45.00	STOP	R1-1	6.25		-			
NAPERVILLE	11028+80.00	LT TN ONLY	R3-5L	5.00				12.5	1
NAPERVILLE	11029+35.00	RT TN ONLY	R3-5R	5		13			
NAPERVILLE	11029+50.00	RT TN ONLY	R3-5R	5		13			
NAPERVILLE	11030+00.00	CUSTOM		5		13			
NAPERVILLE	11031+30.00	RT TN ONLY	R3-5R	5.00		13			
NAPERVILLE	11031+50.00	RT TN ONLY	R3-5R	5.00				12.5	1
NAPERVILLE	11032+85.00	CUSTOM		6.25		15.5			
NAPERVILLE	11034+48.00	STOP	R1-1	6.25		15.5			
NAPERVILLE	11034+48.00	RT TN ONLY	R3-5R	5		-			
NAPERVILLE	11034+71.00	ONE WAY RT	R6-2R	3.00				11.5	1
NAPERVILLE	11034+86.00	STOP	R1-1	6.25		15.5			
NAPERVILLE	11034+86.00	RT TN ONLY	R3-5R	5		-			
NAPERVILLE	11035+58.00	RT TN ONLY	R3-5R	7.5		13.5			
NAPERVILLE	11036+10.00	RT TN ONLY	R3-5R	7.5		13.5			
NAPERVILLE	11036+40.00	ONE WAY RT	R6-2R	3.00				11.5	1
NAPERVILLE	11037+62.00	RT TN ONLY	R3-5R	7.5		13.5			
IDOT				697.54	20.00	1,136.00	34.00	389.00	26.00
DuPage				156.75	60	288	96	48	4
Wheaton				13.75	20	26.5	29	0	0
TOTAL				869	100	1,451	159	437	30

FILE NAME = ...
 USER NAME = tblank
 PLOT DATE = 12/7/2010

DESIGNED - JMM
 DRAWN - TMB
 CHECKED - RMT
 DATE - 12/6/10

REVISED -
 REVISED -
 REVISED -
 REVISED -

benesch

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 7 OF 11 SHEETS STA. TO STA.

F.A.P. RTE. 365 SECTION (57 & 58)WRS-2 COUNTY DUPAGE TOTAL SHEETS 681 SHEET NO. 34 CONTRACT NO. 62419 ILLINOIS FED. AID PROJECT