

**KDSWCD STANDARD NOTES**

1. UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS IN THE ILLINOIS URBAN MANUAL REVISED FEBRUARY 2002.
2. THE KANE-DUPAGE SOIL AND WATER CONSERVATION DISTRICT (KDSWCD) MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITIES, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.
3. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
4. PRIOR TO COMMENCING LAND-DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING BUT NOT LIMITED TO, ADDITIONAL PHASES OF DEVELOPMENT AND OFF-SITE BORROW OR WASTE AREAS) A SUPPLEMENTARY EROSION CONTROL PLAN SHALL BE SUBMITTED TO THE OWNER FOR REVIEW BY THE KDSWCD.
5. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE KDSWCD.
6. DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO SEDIMENT BASINS OR SILT TRAPS. DEWATERING DIRECTLY INTO FIELD TILES OR STORMWATER STRUCTURES IS PROHIBITED.
7. IT IS THE RESPONSIBILITY OF THE LANDOWNER AND/OR GENERAL CONTRACTOR TO INFORM ANY SUB-CONTRACTOR(S) WHO MAY PERFORM WORK ON THIS PROJECT, OF THE REQUIREMENTS IN IMPLEMENTING AND MAINTAINING THESE EROSION CONTROL PLANS AND THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT REQUIREMENTS SET FORTH BY THE ILLINOIS EPA.

**GENERAL NOTES**

1. THE CONSTRUCTION LIMITS WILL BE STAKED BY THE CONTRACTOR PRIOR TO COMMENCING CONSTRUCTION. PAYMENT FOR THIS WORK WILL BE INCLUDED WITHIN THE ITEM CONSTRUCTION LAYOUT, LS. THE CONSTRUCTION LIMITS MAY BE ADJUSTED BY THE ENGINEER TO PRESERVE TREES AND NO ADDITIONAL COMPENSATION WILL BE PAID TO THE CONTRACTOR FOR REVISED CONSTRUCTION LIMITS.
2. THE RESIDENT ENGINEER SHALL HAVE FINAL DETERMINATION OF THE PLACEMENT AND LOCATION OF THE PERIMETER EROSION BARRIER.
3. TEMPORARY DITCH CHECKS SHALL BE ERECTED IN ALL TEMPORARY AND PERMANENT DITCHES. THE RESIDENT ENGINEER SHALL HAVE FINAL DETERMINATION OF THE PLACEMENT, LOCATION AND TYPE OF THE TEMPORARY DITCH CHECKS.
4. SEE DRAINAGE PLANS FOR STORM SEWER INFORMATION. REMOVAL OF EXISTING DRAINAGE ITEMS TO BE COORDINATED WITH STAGE 1 WORK.
5. THE EROSION AND SEDIMENT CONTROL PLANS SHALL BE COORDINATED WITH THE MAINTENANCE OF TRAFFIC SHEETS. THE SEQUENCE OF CONSTRUCTION SHALL BE CONSULTED BEFORE APPLYING EROSION AND SEDIMENT CONTROL MEASURES.
6. COMPLETED SLOPES (SECTIONS OF ROAD EMBANKMENT) SHALL BE SEEDED AND MULCHED AS THE EXCAVATION PROCEEDS TO THE EXTENT CONSIDERED DESIRABLE AND PRACTICAL. BY THE RESIDENT ENGINEER.
7. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR PROLONG FINAL GRADING AND SHAPING SO THAT THE ENTIRE PROJECT CAN BE PERMANENTLY SEEDED AT ONE TIME.
8. PERMANENT EROSION CONTROL MEASURES, PERMANENT SEEDING AND LANDSCAPING IS SHOWN ON THE EROSION AND SEDIMENT CONTROL AND LANDSCAPING PLANS. THE CONTRACTOR SHALL MAINTAIN TEMPORARY EROSION CONTROL MEASURES UNTIL PERMANENT LANDSCAPING SEEDING AND EROSION CONTROL MEASURES CAN BE PLACED.
9. THE CONTRACTOR SHALL PROTECT ALL WETLANDS ADJACENT TO THE RIGHT OF WAY WITH A DOUBLE LAYER OF PERIMETER EROSION BARRIER.
10. ALL STORM SEWER STRUCTURES SHALL BE BUILT TO THE PROPOSED RIM ELEVATIONS SPECIFIED IN THE STORM SEWER SCHEDULES UNLESS A TEMPORARY RIM IS INDICATED IN THE TEMPORARY EROSION CONTROL PLANS.
11. CONSTRUCTION ACTIVITIES AND INSPECTIONS SHALL COMPLY WITH THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP) PREPARED FOR THIS PROJECT.

FILE NAME =	DESIGNED - AAF	REVISED -	<b>benesch</b>	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>TEMPORARY DRAINAGE AND EROSION CONTROL PLANS GENERAL NOTES</b>		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...ND162419-shv-EC-01-GenNote.dgn	DRAWN - TMB	REVISED -					365	(57 & 58)WRS-2	DUPAGE	681	205
USER NAME = tblank	CHECKED - RMT	REVISED -					CONTRACT NO. 62419				
PLOT DATE = 12/7/2010	DATE - 12/6/10	REVISED -					ILLINOIS FED. AID PROJECT				
					SCALE: N.T.S.	SHEET NO. 1	OF 36 SHEETS	STA.	TO STA.		