



CONSTRUCT PROPOSED LATERAL STORM SEWER TO WORK ZONE LIMITS DURING STAGE 1

CONSTRUCT PROPOSED PIPE CULVERT DURING STAGE 1

CONSTRUCT PROPOSED LATERAL STORM SEWER TO WORK ZONE LIMITS DURING STAGE 1

CONSTRUCT PROPOSED CULVERT TO STAGE 1 WORK ZONE LIMITS AND CONNECT TO EXISTING CULVERT

CONSTRUCT PROPOSED LATERAL STORM SEWER TO STAGE 1 WORK ZONE LIMITS

CONSTRUCT PROPOSED LATERAL STORM SEWER TO STAGE 1 WORK ZONE LIMITS TO DRAIN TEMPORARY DITCH

LEGEND:

- PROPOSED MANHOLE
- ⊙ EXISTING MANHOLE
- PROPOSED CATCH BASIN
- EXISTING CATCH BASIN
- ↔ HIGH POINT
- △ EXISTING FLARED END SECTION
- ▲ PROPOSED FLARED END SECTION
- ~ FLOW LINE FOR PROPOSED DITCH
- PROPOSED DRAINAGE INLET
- ▬ PERIMETER EROSION BARRIER, 28000400
- ▬ PROPOSED UNDERDRAIN
- ▬ EXISTING STORM SEWER
- ▬ PROPOSED STORM SEWER
- ▬ WETLAND
- ⌒ CULVERT INLET PROTECTION - STONE
- XX006722 - TEMPORARY AGGREGATE BERM - RIPRAP
- XX006723 - TEMPORARY AGGREGATE BERM - COURSE AGGREGATE
- ◇ INLET & PIPE PROTECTION, 28000500
- ◇ TEMPORARY DITCH CHECK, 28000305
- ◆ PERMANENT DITCH CHECK WITH 12" PIPE OUTLET
- INLET FILTERS, 28000510
- Ⓞ SEDIMENT BASIN, 28000200
- TEMPORARY EROSION CONTROL SEEDING, 28000250 AND MULCH, METHOD 2, 25100115
- WORK ZONE LIMITS
- TEMPORARY PAVEMENT
- STABILIZED CONSTRUCTION ENTRANCE, X0322671

NOTE:

ALL STORM SEWER AND PIPE CULVERTS BUILT ONLY TO STAGE 1 LIMITS SHALL BE PLUGGED AND BURIED, UNLESS NOTED TO DRAIN TEMPORARY DITCH OR FOR CONNECTION TO EXISTING SEWER OR CULVERT.

FILE NAME =	DESIGNED - AAF	REVISED -
...\\0162419-ah-EC-27-IL56.staging\1-26.dgn	DRAWN - TMB	REVISED -
USER NAME = tblank	CHECKED - RMT	REVISED -
PLOT DATE = 12/7/2010	DATE - 12/6/10	REVISED -

benesch

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**TEMPORARY DRAINAGE AND EROSION CONTROL PLANS
STAGE 1**

SCALE: 1"=50' SHEET NO. 7 OF 36 SHEETS STA. 318+00 TO STA. 333+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	157 & 581WRS-2	DUPAGE	681	211
ILLINOIS FED. AID PROJECT			CONTRACT NO. 62419	