



**LEGEND**

- |  |  |
|--|--|
| ① THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS (WHITE) | ⑧ RECESSED REFLECTIVE PAVEMENT MARKER (1-WAY CRYSTAL / OPAQUE) (SEE SHEET NO. 421) |
| ② THERMOPLASTIC PAVEMENT MARKING - LINE 4" (WHITE)             | ⑨ THERMOPLASTIC PAVEMENT MARKING - LINE 12" (YELLOW)                               |
| ③ THERMOPLASTIC PAVEMENT MARKING - LINE 4" (YELLOW)            | ⑩ THERMOPLASTIC PAVEMENT MARKING - LINE 4" (WHITE) (10' DASH, 30' SKIP)            |
| ④ THERMOPLASTIC PAVEMENT MARKING - LINE 6" (WHITE)             | ⑪ THERMOPLASTIC PAVEMENT MARKING - LINE 6" (WHITE) ( 2' DASH, 6' SKIP)             |
| ⑤ THERMOPLASTIC PAVEMENT MARKING - LINE 12" (WHITE)            | ⑫ THERMOPLASTIC PAVEMENT MARKING - LINE 6" (YELLOW)                                |
| ⑥ THERMOPLASTIC PAVEMENT MARKING - LINE 24" (WHITE)            | ⑬ THERMOPLASTIC PAVEMENT MARKING - LINE 8" (WHITE)                                 |
| ⑦ RAISED REFLECTIVE PAVEMENT MARKER (1-WAY CRYSTAL / OPAQUE)   |  |

EXISTING SIGN

PROPOSED SIGN

OFFSETS ARE GIVEN TO SIGN POST

FILE NAME =	DESIGNED - JMM	REVISED -	<b>benesch</b>	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PAVEMENT MARKING AND SIGNING PLAN NAPERVILLE RD</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...\\D162419-shu-pmsign017.dgn	DRAWN - TMB	REVISED -			365	(57 & 58)WRS-2	DUPAGE	681	322			
USER NAME = tblank	CHECKED - RMT	REVISED -			SCALE: 1"=50' SHEET NO.17 OF 19 SHEETS STA. POB TO STA. 1019+00			CONTRACT NO. 62419				
PLOT DATE = 12/7/2010	DATE - 12/6/10	REVISED -			ILLINOIS FED. AID PROJECT							