



TEMPORARY WIRELESS INTERCONNECT TO CROMWELL DR (WEST), EAST LOOP RD (EAST), AND DANADA SQ (NORTH)

TEMPORARY MASTER CONTROLLER

AERIAL CABLE TO SERVICE POLE

IL RTE 56 (BUTTERFIELD RD)

MATCH LINE 397+75 SEE SHEET

IL RTE 56 (BUTTERFIELD RD)

NAPERVILLE RD

CONSTRUCTION NOTES:

- ① THE CONTRACTOR SHALL BAG LEFT-TURN ARROWS ON ALL 5-SECTION HEADS DURING CONSTRUCTION STAGES THAT REQUIRE PROTECTED ONLY LEFT-TURN PHASING (LEAD-LAG) OR WHEN DUAL LEFT-TURN OPERATION IS IMPLEMENTED.
- ② THE PRESTAGE AND STAGE 3 WILL REQUIRE LEAD/LAG PROTECTED LEFT-TURN OPERATIONS FOR EB AND WB IL-56 LEFT-TURNS. THE CONTRACTOR SHALL BAG LEFT-TURN ARROWS ON ALL 5 SECTION HEADS DURING THESE STAGES.
- ③ THE CONTRACTOR SHALL PROVIDE TEMPORARY NEAR-RIGHT SIGNALS ATTACHED TO BARREL MOUNTED WOOD POSTS (MIN 6" x 6") AS SHOWN ON THE PLAN. CONTRACTOR SHALL FURNISH ENOUGH SLACK TO RELOCATE POSTS AND SIGNALS TO ANY LOCATIONS REQUIRED TO MATCH THE CONSTRUCTION STAGING PLAN AND BE VISIBLE TO RIGHT-TURNING VEHICLES. RELOCATION OF POSTS AND SIGNALS IS INCIDENTAL TO TEMPORARY TRAFFIC SIGNAL.

THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACT BID PRICE.

- 2.0 EACH SIGNAL HEAD, 1-FACE, 3-SECTION
- 2.0 EACH SIGNAL HEAD, 2-FACE, 1-3-SECTION, 1-5-SECTION
- 2.0 EACH SIGNAL HEAD, 3-FACE, 2-3-SECTION, 1-5-SECTION
- 4.0 EACH MAST ARM ASSEMBLYS
- 4.0 EACH 5-SECTION MAST ARM MOUNT
- 4.0 EACH SIGNAL POST
- 1.0 EACH SERVICE INSTALLATION
- 1.0 EACH CONTROLLER AND CABINET, COMPLETE
- 5.0 EACH BACKPLATE

NOTE:
THE TEMPORARY TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

NOTE:
FOR TEMPORARY TRAFFIC SIGNAL GENERAL NOTES, SEE SHEET 243

FILE NAME =	DESIGNED - GHT	REVISED -
...\\sl62419-shv-ts-temp4.dgn	DRAWN - BDW	REVISED -
USER NAME = tblank	CHECKED - MPM	REVISED -
PLOT DATE = 12/7/2010	DATE - 12/6/10	REVISED -

benesch

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**TEMPORARY TRAFFIC SIGNAL
AND REMOVAL PLAN
IL RTE 56 AND NAPERVILLE RD**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(57 & 58)WRS-2	DUPAGE	681	358
				CONTRACT NO. 62419
ILLINOIS FED. AID PROJECT				

SCALE: 1"=20' SHEET NO.15 OF 27 SHEETS STA. TO STA.