

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE														
				URBAN	NHF		CMF		CMF				NHF		NHF			
					0003 ROADWAY IL. RTE. 56	0004 FERRY CREEK CULVERT	0010 DUPAGE RIVER BRIDGE	0014 PRAIRIE PATH BRIDGE	0021 T.S. AT IL. RTE. 59	0021 T.S. AT BATAVIA RD. 80% FEDERAL 10% STATE 10% C.O.W.	0021 T.S. AT WINFIELD RD. 80% FEDERAL 10% STATE 10% DuPAGE	0021 INTERCONNECT IL. RTE. 56	0021 ROADWAY LIGHTING	0021 SIGNING	0031 LANDSCAPE	0043		
50200100	STRUCTURE EXCAVATION	CU YD	1,192		250		942											
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	662			662												
50300225	CONCRETE STRUCTURES	CU YD	520.0		62.8		404.2	53.0										
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,452.9				1,166.2	286.7										
50300260	BRIDGE DECK GROOVING	SQ YD	2,080				2,080											
50300280	CONCRETE ENCASEMENT	CU YD	35.5				35.5											
50300300	PROTECTIVE COAT	SQ YD	3,089				3,089											
50400905	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 42 IN.	FOOT	2,916				2,916											
50500505	STUD SHEAR CONNECTORS	EACH	836		836													
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	421,410		11,800	63,190	275,050	71,370										
50800515	BAR SPLICERS	EACH	1,406			94	1,030	282										
50901720	BICYCLE RAILING	FOOT	225				225											
50901750	PARAPET RAILING	FOOT	225				225											
51201800	FURNISHING STEEL PILES HP 14 x 73	FOOT	1,729				1,729											
51202000	FURNISHING STEEL PILES HP 14 x 102	FOOT	1,032				1,032											
51202305	DRIVING PILES	FOOT	2,761				2,761											
51203800	TEST PILE STEEL HP 14 x 73	EACH	2				2											
51204000	TEST PILE STEEL HP 14 x 102	EACH	1				1											
51204650	PILE SHOES	EACH	65				65											
51500100	NAME PLATES	EACH	1				1											
54003000	CONCRETE BOX CULVERTS	CU YD	204.7			204.7												
54020603	PRECAST CONCRETE BOX CULVERTS 6' x 3' (M273)	FOOT	594		594													
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	24		24													
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	299		299													
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	346		346													
542A0259	PIPE CULVERTS, CLASS A, TYPE 1 54"	FOOT	83		83													
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	143		143													
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	214		214													
542A1012	PIPE CULVERTS, CLASS A, TYPE 1 12" (TEMPORARY)	FOOT	200		200													
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	43		43													
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	17		17													
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	10		10													
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	9		9													
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2		2													
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1		1													
54213699	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54"	EACH	4		4													
54214743	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 48"	EACH	1		1													
54214749	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 54"	EACH	1		1													
54216200	REINFORCED CONCRETE PIPE TEE, 24" PIPE WITH 12" RISER	EACH	1		1													
54216220	REINFORCED CONCRETE PIPE TEE, 36" PIPE WITH 12" RISER	EACH	2		2													

Rev. 1-7-11