

# SUMMARY OF QUANTITIES

			CONSTRUCTION TYPE CODE													
			URBAN		NHF			CMF		NHF				TE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0003 ROADWAY IL. RTE. 56 80% FEDERAL 20% STATE	0004 FERRY CREEK CULVERT 80% FEDERAL 20% STATE	0010 DUPAGE RIVER BRIDGE 80% FEDERAL 20% STATE	0014 PRAIRIE PATH BRIDGE 80% FEDERAL 20% STATE	0021 T.S. AT IL. RTE. 59 80% FEDERAL 20% STATE	0021 T.S. AT BATAVIA RD. 80% FEDERAL 10% STATE 10% C.O.W.	0021 T.S. AT WINFIELD RD. 80% FEDERAL 10% STATE 10% DUPAGE	0021 INTERCONNECT IL. RTE. 56 80% FEDERAL 20% STATE	0021 ROADWAY LIGHTING 80% FEDERAL 20% STATE	0021 SIGNING 80% FEDERAL 20% STATE	0031 LANDSCAPE 80% FEDERAL 20% STATE	0043 80% FED. 20% WARRENVILLE	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	68,226	68,226												
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	20,911	20,911												
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	443	443												
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	7,246	7,246												
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,047	1,047												
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,610	1,610												
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	96	96												
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	157	157												
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	122	122												
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,407	1,407												
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	20	20												
* 78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	860	860												
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	42	42												
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	16	16												
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8												
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	3,000	3,000												
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3,000	3,000												
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1												
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1												
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	6,331	6,331					1,063	580	1,220	3,468				
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	459	459					134	213	112					
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	114	114					18	44	52					
* 81000900	CONDUIT IN TRENCH, 3 1/2" DIA., GALVANIZED STEEL	FOOT	39	39						29	10					
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	967	967					106	77	92					650
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	707	707					274	53	236					
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	3,058	3,058					560	991	601					
* 81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	224	224								224				
* 81400100	HANDHOLE	EACH	18	18					4	6	3	1				4
* 81400200	HEAVY-DUTY HANDHOLE	EACH	19	19					6	2	6	5				
* 81400300	DOUBLE HANDHOLE	EACH	9	9					2	4	3					
* 81603210	UNIT DUCT, 600V, 3-1/C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	4,800	4,800								4,800				
* 81701375	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C 300MCM	FOOT	66	66								66				
* 81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	6,260	6,260								6,260				
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	11,622	11,622					1,255	922	1,427	3,468				650
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	52	52								52				
* 83050825	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. DAVIT ARM	EACH	20	20								20				
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15 FT. MAST ARM	EACH	16	16								16				
* 83057356	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH TWO 15 FT. MAST ARMS	EACH	3	3								3				
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	190	190								190				
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	20	20								20				

\* SPECIALTY ITEM

FILE NAME = 0162420-sh1-500.dgn  
 PLOT DATE = 12/3/2010  
 PLOT SCALE = 5/8" = 1' IN.

**CHRISTIAN-ROGE & ASSOCIATES, INC.**  
 ENGINEERS-PLANNERS-SURVEYORS  
 211 WEST WACKER DRIVE  
 CHICAGO, ILLINOIS 60606  
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.	REVISED -
DRAWN - A.C.S.	REVISED -
CHECKED - M.P.	REVISED -
DATE - DECEMBER 3, 2010	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**  
**IL. RTE. 56**

SCALE: NONE    SHEET NO. 7 OF 12 SHEETS    STA. 90+00    TO STA. 255+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(58&59) WRS-3	DUPAGE	466	11
CONTRACT NO. 62420				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev. 1-7-11