

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE													
			URBAN	NHF			CME		CONSTRUCTION TYPE CODE				NHF		0043	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0003 ROADWAY IL. RTE. 56 80% FEDERAL 20% STATE	0004 FERRY CREEK CULVERT 80% FEDERAL 20% STATE	0010 DUPAGE RIVER BRIDGE 80% FEDERAL 20% STATE	0014 PRAIRIE PATH BRIDGE 80% FEDERAL 20% STATE	0021 T.S. AT IL. RTE. 59 80% FEDERAL 20% STATE	0021 T.S. AT BATAVIA RD. 80% FEDERAL 10% STATE 10% C.O.W.	0021 T.S. AT WINFIELD RD. 80% FEDERAL 10% STATE 10% DUPAGE	0021 INTERCONNECT IL. RTE. 56 80% FEDERAL 20% STATE	0021 ROADWAY LIGHTING 80% FEDERAL 20% STATE	0021 SIGNING 80% FEDERAL 20% STATE	0031 LANDSCAPE 80% FEDERAL 20% STATE	0043 100% CITY OF WARRENVILLE	
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	19													
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	12													
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	12													
* 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1													
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1													
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1								1					
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1							1						
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1					1								
* 85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1						1							
* 86000100	MASTER CONTROLLER	EACH	1								1					
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	3					1	1	1						
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	5,495					859	1,358	3,278						
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	11,191					2,037	6,222	2,932						
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	12,624					3,241	6,162	3,221						
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	4,111					2,035		2,076						
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	12,379					4,953	2,962	4,464						
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	102					42	28	32						
* 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	3						3							
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	4						4							
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1							1						
* 87700120	STEEL MAST ARM ASSEMBLY AND POLE, 16 FT.	EACH	5					3		2						
* 87700130	STEEL MAST ARM ASSEMBLY AND POLE, 18 FT.	EACH	2						1	1						
* 87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1						1							
* 87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1					1								
* 87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1													
* 87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	2						2							
* 87700330	STEEL MAST ARM ASSEMBLY AND POLE, 56 FT.	EACH	1						1							
* 87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	2													
* 87700404	STEEL MAST ARM ASSEMBLY AND POLE, 62 FT.	EACH	1													
* 87700400	STEEL MAST ARM ASSEMBLY AND POLE, 64 FT.	EACH	1													
* 87700414	STEEL MAST ARM ASSEMBLY AND POLE, 66 FT.	EACH	1							1						
* 87700418	STEEL MAST ARM ASSEMBLY AND POLE, 68 FT.	EACH	1							1						
* 87700428	STEEL MAST ARM ASSEMBLY AND POLE, 74 FT.	EACH	1							1						
* 87704170	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 48 FT. (SPECIAL)	EACH	1					1								
* 87704188	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 54 FT. (SPECIAL)	EACH	2					2								
* 87704190	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 55 FT. (SPECIAL)	EACH	1					1								
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	28						24	4						
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	12					4	4	4						
* 87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIAMETER	FOOT	90					40	20	30						
* 87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	101					58	43							

* SPECIALTY ITEM

FILE NAME = 0162420-sh1-500.dgn
 PLOT DATE = 12/3/2010
 PLOT SCALE = 50.0000 / IN.



CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.
 DRAWN - A.C.S.
 CHECKED - M.P.
 DATE - DECEMBER 3, 2010

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
 IL. RTE. 56**

SCALE: NONE SHEET NO. 8 OF 12 SHEETS STA. 90+00 TO STA. 255+00

F.A.P. RTE. 365	SECTION (58&59) WRS-3	COUNTY DUPAGE	TOTAL SHEETS 466	SHEET NO. 12
CONTRACT NO. 62420				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev. 1-7-11