



- LEGEND**
- 716.81 - PROPOSED ELEVATION @ 25, 50' OR 100' INTERVALS
  - - PROPOSED CATCH BASIN LOCATION
  - ▨ - PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH
  - ▤ - DETECTABLE WARNINGS
  - - LANE LINE

HMA PAVEMENT (FULL DEPTH), 14" (TYP.)  
 POLYMERIZED HMA SURFACE COURSE, STONE MATRIX ASPHALT, N80, 2"  
 POLYMERIZED HMA BINDER COURSE, STONE MATRIX ASPHALT, N80, 2"  
 POLYMERIZED HMA BINDER COURSE, IL-19.0, N90, 10"

CONCRETE CURB & GUTTER, TYPE B-6.12 &  
 HMA MEDIAN (4" THICK) (TYP. @ WINFIELD RD.)

FILE NAME = D162420-sh1-intersec08.dgn  
 PLOT DATE = 12/29/2010  
 PLOT SCALE = 20,000' / 1"

**CHRISTIAN-ROGE & ASSOCIATES, INC.**  
 ENGINEERS-PLANNERS-SURVEYORS  
 211 WEST WACKER DRIVE  
 CHICAGO, ILLINOIS 60606  
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.	REVISED 1 - ADDENDUM 1 12-28-2010
DRAWN - B.K.	REVISED -
CHECKED - M.P.	REVISED -
DATE - DECEMBER 3, 2010	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**DETAILS AND ELEVATIONS  
 WINFIELD ROAD**

SCALE: 1" = 20' SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(58&59) WRS-3	DuPAGE	466	115
CONTRACT NO. 62420				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				