



INTERCONNECT SCHEDULE OF QUANTITIES

ITEM	UNIT	QUANTITY
CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	357
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	357
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
DRILL EXISTING HANDHOLE	EACH	1
REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	3500
ELECTRIC CABLE IN CONDUIT, TRACER NO. 14 1C	FOOT	2284
RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM - LEVEL 1	EACH	1
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	2296

REVISED 12-20-10

TS-27

FILE NAME = TS-34.dgn
PLOT DATE = 12/23/2010

SPAAN Tech, Inc.
311 S. Wacker Drive, Suite 2400 Chicago, IL 60606
phone: 312.277.8800 fax: 312.277.8808 web: www.spaan7.com

DESIGNED - R.A.S.	REVISED -
DRAWN - D.L.	REVISED -
CHECKED - A.D.O.	REVISED -
DATE - AUGUST 2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

INTERCONNECT SCHEMATIC AND SCHEDULE OF QUANTITIES

IL ROUTE 59
IL ROUTE 56 (BUTTERFIELD ROAD) TO INGALTON AVENUE

SCALE: NONE	SHEET NO. OF SHEETS	STA. TO STA.
-------------	---------------------	--------------

F.A.P. RTE. 365	SECTION (58859) WRS-3	COUNTY DuPAGE	TOTAL SHEETS 466	SHEET NO. 310
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				CONTRACT NO. 62420