

# SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE																
			URBAN	NHF			CMF		CMP				NHF			TE			
			TOTAL QUANTITIES	0003 ROADWAY IL. RTE. 56	0004 FERRY CREEK CULVERT	0010 DUPAGE RIVER BRIDGE	0014 PRAIRIE PATH BRIDGE	0021 T.S. AT IL. RTE. 59	0021 T.S. AT BATAVIA RD.	0021 T.S. AT WINFIELD RD.	0021 INTERCONNECT IL. RTE. 56	0021 ROADWAY LIGHTING	0021 SIGNING	0031 LANDSCAPE	0043				
	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 10% STATE 10% C.O.W.	80% FEDERAL 10% STATE 10% DUPAGE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE						
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	68,226	68,226															
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	20,911	20,911															
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	443	443															
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	7,246	7,246															
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,047	1,047															
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,610	1,610															
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	96	96															
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	157	157															
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	122	122															
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,407	1,407															
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	20	20															
* 78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	860	860															
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	42	42															
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	16	16															
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8															
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	3,000	3,000															
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3,000	3,000															
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1																
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1																
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	6,319						1,063	580	1,208	3,468							
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	432						134	213	85								
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	108						18	44	46								
* 81000900	CONDUIT IN TRENCH, 3 1/2" DIA., GALVANIZED STEEL	FOOT	39							29	10								
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	947						106	77	72								650
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	727						274	53	256	144							
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	3,030						560	991	573								
* 81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	224									224							
* 81400100	HANDHOLE	EACH	18						4	6	3	1							4
* 81400200	HEAVY-DUTY HANDHOLE	EACH	19						6	2	6	5							
* 81400300	DOUBLE HANDHOLE	EACH	9						2	4	3								
* 81603210	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	4,800																4,800
* 81701375	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C 300MCM	FOOT	66																66
* 81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	6,260																6,260
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	11,586						1,255	922	1,391	3,468							3,900
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	52																52
* 83050825	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. DAVIT ARM	EACH	20																20
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15 FT. MAST ARM	EACH	16																16
* 83057356	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH TWO 15 FT. MAST ARMS	EACH	3																3
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	190																190
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	20																20

\* SPECIALTY ITEM

FILE NAME = D:\62420\sh-500.dgn  
 PLOT DATE = 12/3/2010  
 PLOT SCALE = 5/8" = 1' / IN.



DESIGNED - S.J.P.	REVISED -
DRAWN - A.C.S.	REVISED -
CHECKED - M.P.	REVISED -
DATE - DECEMBER 3, 2010	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
IL. RTE. 56**

SCALE: NONE SHEET NO. 7 OF 12 SHEETS STA. 90+00 TO STA. 255+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(58&59) WRS-3	DUPAGE	466	11
<b>CONTRACT NO. 62420</b>				
<small>FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT</small>				