STRUCTURE NUMBER	STATION	OFFSET	TRENCH BACKFILL	STORM SEWER, CLASS A, TYPE 1						STORM SEWER, CLASS A, TYPE 2							STORM SEWER, CLA T1 EQRS			STORM SEWER, CLA T2 EQRS		STORM SEWER (WMQ)			CATCH BASINS, TYPE A 4'Ø					CATCH BASINS, TYPE A 5'Ø			CATCH BASINS, TYPE C		MANHOLES, TYPE A 4'Ø			MANHOLES, TYPE A 5'Ø			MANHOLES, TYPE A 6'Ø		MANHOLES TYPE A w/RESTRICTOR PLATE			MANHOLES, TYPE A 8'DIA.		INLETS TYPE A
				12"	15"	18"	24"	30"	36"	12"	15"	18"	24"	30"	36"	42"		42"	54"	42"	48"	12"	15"	18"	TY 1F OL	TY 8G	TY 11V F&G	TY 23 F&G	TY 24 F&G	TY 23 F&G	TY 24 F&G	W/MED. INL (604101)	TY 1F OL	TY 8G	TY 1F CL	TY 8G	TY 24 F&G	TY 1F CL	TY 8G		TY 1F CL	TY 8G	6'Ø TY 1F CL	7'Ø TY 1F CL	8'Ø TY 1F CL	TY 1F CL	TY 8G	TY 8G
			CU YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH		EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
IL. RTE. 56																																															
1	89+45	13 R					14																													1										
2	90+53	16 R											102																				1													
3	90+53	7 R		6																															1										
4	90+58	6.5 R		12																								1																	
5	92+30	31 R								9															1																				
6	92+72	31 L	8.8							36																		1																	
7	92+72	3.3 R								6																		1																	
8	92+70	16 R						214		6																									1										
9	92+70	26 R											208																				1													
10	94+45	33.1 L	13							50																		1																	
11	94+45	18 R								6																		1																	
12	94+45	31 R										172																							1										
13	96+40	67 R	20.9								190														1																				
14	96+95	35.7 L	7.8							33																		1																	
15	96+95	0 R	7.8							34															1																				
16	96+95	36.7 R									62																		1																
17	102+43	9 R	7.3							51																1																				
18	108+35	9 L	1.4							12																1																				
19	108+50	9 L	11.6							69																1																				
EX	109+10	70 L	20.4								185																																			
20	108+80	62 L	16.3								212														1																				
21	112+30	9 R	1.4							6																1																				
22	119+25	105 L	2.4																			20																							1
23	119+00	3 L	24.4						60																										1										
23	119+00	3 L	32.4						70																																			
24	120+00	9 L	32.7	96																						1																				
25	120+25	9 L	6.4	21																						1																				
26	122+08	70 R	11.7									12																																	1		
26	122+08	70 R	101.8																		164																									
26	122+08	70 R	47.5																180																											
27	122+77	81 R		6																					1																				
28	123+60	9 R	5.4							21																1																				
29	123+85	9 R	8.5								36															1																				
30	123+85	49 R									21																	1																	
31	123+96	70 R	103.8																421																									1		
32	124+00	82 R		6																													1												
33	124+90	9 R	12.6	60																						1																				
34	126+00	90 R		10																													1												
35	126+55	90 R		10																													1												
36	127+40	90 R		6																													1												
37	127+75	90 R		6																													1												
38	122+32	100.3 L	12.7																				76											1											
39	122+72	53.2 L								21												1																								
40	123+06	65 L																		290																								1		
41	126+00	65 L																		292																								1		
42	129+00	65 L	86.7																	396																								1		
43	130+00	0 R	17.4							58															1																				
44	132+00	63 L																		392																							1		
45	136+00	62 L	134.4															468																										1		
46	136+00	0 R	9.9							52															1																				
47	139+75	0 R	18.5							49															1																				
48	140+75	51 L	322.7															396																										1		
49	144+75	51 L	4.2					12																																			1		
50	144+90	49 L						9																																				
50	144+90	49 L	32.1										42																																
51	144+70	9 L	5.6							20																1																				
52	144+90	3 L	51.5										71																				1												
53	148+00	9 R	12.7							54																1																				
54	148+60	15 R	11.6							63																		1																	
55	149+85	7 R	3.1							12																		1																	
56	150+00	5.9 R	17.2							65																		1																	
57	150+15	4.7 R	3.1							12																		1																	
58	151+10	1.4 L	36							76																		1																	
59	153+30	9 L	21.1							85																		1																	
60	154+94	72.5 R																										1																

CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

FILE NAME = D162420-sht-schedule4.dgn
PLOT DATE = 12/2/2010
PLOT SCALE = 50.0000 ' / IN.

DESIGNED	-	S.J.P.	REVISED -
DRAWN	-	A.C.S.	REVISED -
CHECKED	-	M.P.	REVISED -
DATE	-	DECEMBER 3, 2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
IL. RTE. 56

SCALE: NONE | SHEET NO. 4 OF 7 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(58&59) WRS-3	DuPAGE	466	28
		CONTRACT NO. 62420		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		