



DESCRIPTION	ALIGNMENTS			PERMANENT SURVEY MARKERS, TYPE I	PERMANENT SURVEY MARKERS, TYPE II
	STATION	NORTHING	EASTING		
<b>ILLINOIS ROUTE 56</b>					
P. I.	84+99.93	1,877,258.88	1,015,894.68		
P. C.	91+52.68	1,877,270.32	1,016,547.32		1
P. I.	95+35.20	1,877,277.02	1,016,929.78		
P. T.	99+17.57	1,877,265.33	1,017,312.12		1
P. I.	107+58.46	1,877,239.63	1,018,152.62	1	
P. I.	116+35.08	1,877,212.84	1,019,028.83	1	
P. I.	126+33.92	1,877,182.31	1,020,027.20	1	
P. C.	144+07.82	1,877,133.51	1,021,800.43	1	
P. I.	152+72.86	1,877,109.72	1,022,665.14		
P. T.	161+00.48	1,877,509.78	1,023,432.10		1
P. C.	190+01.95	1,878,851.66	1,026,004.63		1
P. I.	196+27.61	1,879,141.02	1,026,559.36		
P. T.	202+46.80	1,879,558.14	1,027,025.68		1
P. C.	207+76.71	1,879,911.42	1,027,420.64		1
P. I.	221+81.44	1,880,847.95	1,028,467.63		
P. T.	234+46.95	1,880,795.22	1,029,871.37		1
P. C.	239+23.56	1,880,777.32	1,030,347.64		1
P. I.	251+32.09	1,880,731.96	1,031,555.32		
P. O. C.	255+00.00	1,880,817.90	1,031,922.50		1
P. T.	263+33.07	1,880,919.71	1,032,749.18		
<b>ILLINOIS ROUTE 59</b>					
P. O. T.	500+00.00	1,875,523.25	1,019,235.56		
P. C.	502+91.54	1,875,813.87	1,019,258.63		
P. I.	504+02.27	1,875,924.26	1,019,267.39		
P. T.	505+12.61	1,876,032.17	1,019,292.27	1	
P. I.	509+79.40	1,876,487.03	1,019,397.13	1	
P. I.	524+53.79	1,877,926.79	1,019,714.82	1	
P. I.	527+08.43	1,878,176.18	1,019,766.25	1	
P. O. T.	534+94.18	1,878,942.89	1,019,938.18		
<b>BATAVIA ROAD</b>					
P. O. T.	600+00.00	1,878,021.04	1,026,985.37		
P. I.	608+22.92	1,878,425.05	1,026,268.45		
P. I.	612+42.84	1,878,631.59	1,025,902.83		
P. I.	615+95.91	1,878,805.02	1,025,595.30		
P. O. T.	629+28.08	1,879,462.77	1,024,436.83		
<b>WINFIELD ROAD</b>					
P. O. T.	700+00.00	1,878,695.91	1,029,195.21		
P. I.	710+00.03	1,879,695.72	1,029,215.88		
P. C.	723+02.62	1,880,998.17	1,029,234.98		
P. I.	726+29.86	1,881,325.38	1,029,239.78		
P. T.	729+53.77	1,881,643.85	1,029,164.55		
P. O. T.	733+64.00	1,882,043.09	1,029,070.23		
P. O. T.	740+73.81	1,882,733.88	1,028,907.04		

FILE NAME = D162420-sht-align3.dgn  
 PLOT DATE = 12/2/2010  
 PLOT SCALE = 250.000' / IN.

**CHRISTIAN-ROGE & ASSOCIATES, INC.**  
 ENGINEERS-PLANNERS-SURVEYORS  
 211 WEST WACKER DRIVE  
 CHICAGO, ILLINOIS 60606  
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.	REVISED -
DRAWN - B.K.	REVISED -
CHECKED - M.P.	REVISED -
DATE - DECEMBER 3, 2010	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**ALIGNMENT PLAN AND TIES**  
**IL RTE. 56**

SCALE: NONE SHEET NO. 3 OF 3 SHEETS STA. TO STA.

F.A.P. RTE. 365	SECTION (58059) WRS-3	COUNTY DuPAGE	TOTAL SHEETS 466	SHEET NO. 34
CONTRACT NO. 62420				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				