



CONSTRUCTION LEGEND

- WORK ZONE
- CONSTRUCTION LIMITS

NOTE: TEMPORARY DITCH CHECKS SHALL BE INSTALLED AT 100' INTERVALS AND PROVIDE A ONE FOOT DEPTH UNLESS OTHERWISE NOTED.

- NOTE:
- INSTALL 18 INLET FILTERS THIS SHEET.
 - THE CONTRACTOR SHALL MAINTAIN STREAM FLOW IN ACCORDANCE WITH THE SWPPP.

EROSION CONTROL LEGEND

- PERIMETER EROSION BARRIER
- PERIMETER EROSION BARRIER, SPECIAL
- INLET AND PIPE PROTECTION OR HEADWALL PROTECTION
- TEMPORARY DITCH CHECK (SEE NOTE)
- RIPRAP
- ROCK CHECK DAM
- SEDIMENT BASIN (50' x 10' x 1' DEPTH)
- TURF REINFORCEMENT MAT

FILE NAME = D162428-ahc-ec2-3.dgn
 PLOT DATE = 12/2/2010
 PLOT SCALE = 50.000' / 1"

CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

| | |
|-------------------------|-----------|
| DESIGNED - S.J.P. | REVISED - |
| DRAWN - B.K. | REVISED - |
| CHECKED - M.P. | REVISED - |
| DATE - DECEMBER 3, 2010 | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

EROSION AND SEDIMENT CONTROL PLAN - STAGE II
IL. RTE. 56

SCALE: 1" = 50' SHEET NO. 3 OF 6 SHEETS STA. 144+00 TO STA. 174+00

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---------------|--------|--------------------|-----------|
| 365 | (58&59) WRS-3 | DuPAGE | 466 | 73 |
| FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | | CONTRACT NO. 62420 | |