

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	(12&13)WRS-4	WILL	608	7
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

URBAN

FUNDING BREAKDOWN		80% FED 20% STATE	80% STATE 20% FPDWC	80% STATE 20% VOF	80% STATE 20% VOF	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% VOF	80% FED 20% STATE	80% FED 13.3% STATE 6.7% VOF	80% FED 10% STATE 10% FT	80% FED 10% STATE 5% VOF 5% FT	80% FED 20% STATE	80% FED 20% STATE
LOCATION OF WORK		ROADWAY	BIKEPATH	BIKEPATH	SIDEWALK	SIDEWALK	HICKORY CREEK BRIDGE	BOX CULVERTS	LIGHTING	LANDSCAPING	WATERMAIN	WATERMAIN	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	INTERCONNECT
SUMMARY OF QUANTITIES																			
CODE NO.	PAY ITEM	UNIT	TOTAL	0003	0021	0021	0021	0021	0013	0040	0021	0031	0043	0043	0021	0021	0021	0021	0021
50901750	PARAPET RAILING	FOOT	216						216										
51201610	FURNISHING STEEL PILES HP12X63	FOOT	910						910										
51201700	FURNISHING STEEL PILES HP12X74	FOOT	665						665										
51202305	DRIVING PILES	FOOT	1575						1575										
51203610	TEST PILE STEEL HP12X63	EACH	2						2										
51203700	TEST PILE STEEL HP12X74	EACH	1						1										
51204650	PILE SHOES	EACH	48						48										
51500100	NAME PLATES	EACH	2						1	1									
52000110	PREFORMED JOINT STRIP SEAL	FOOT	224						224										
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	9						9										
52100520	ANCHOR BOLTS, 1"	EACH	72						72										
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	1							1									
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2							2									
54001003	BOX CULVERT END SECTIONS, CULVERT NO. 3	EACH	3							3									
54001004	BOX CULVERT END SECTIONS, CULVERT NO. 4	EACH	2							2									
54002020	EXPANSION BOLTS 3/4 INCH	EACH	33							33									
54003000	CONCRETE BOX CULVERTS	CU YD	58.4							58.4									
54010302	PRECAST CONCRETE BOX CULVERTS 3' X 2'	FOOT	275							275									
54010402	PRECAST CONCRETE BOX CULVERTS 4' X 2'	FOOT	1,145							1,145									
54010704	PRECAST CONCRETE BOX CULVERTS 7' X 4'	FOOT	2,102							2,102									
54010903	PRECAST CONCRETE BOX CULVERTS 9' X 3'	FOOT	118							118									
54010905	PRECAST CONCRETE BOX CULVERTS 9' X 5'	FOOT	519							519									
54011005	PRECAST CONCRETE BOX CULVERTS 10' X 5'	FOOT	620							620									
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	19							19									
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	8							8									
542D5503	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND - SIZE 48"	FOOT	52	52															
5421A024	PIPE CULVERTS, CLASS A, TYPE 1 24" (TEMPORARY)	FOOT	46	46															
5421A030	PIPE CULVERTS, CLASS A, TYPE 1 30" (TEMPORARY)	FOOT	42	42															
5421D012	PIPE CULVERTS, CLASS D, TYPE 1 12" (TEMPORARY)	FOOT	190	190															
5421D015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	90	90															
5421D018	PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)	FOOT	90	90															

● INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE 6/11/2010

DRAWN BY JRR CHECKED BY JRV