

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	(12&13)WRS-4	WILL	608	11
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

URBAN

SUMMARY OF QUANTITIES		FUNDING BREAKDOWN		80% FED 20% STATE	80% STATE 20% FPDWC	80% STATE 20% VOF	80% STATE 20% VOF	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% VOF	80% FED 20% STATE	80% FED 13.3% STATE 6.7% VOF	80% FED 10% STATE 10% FT	80% FED 10% STATE 5% VOF 5% FT	80% FED 20% STATE	80% FED 20% STATE	
CODE NO.	PAY ITEM	UNIT	TOTAL	ROADWAY	BIKEPATH	BIKEPATH	SIDEWALK	SIDEWALK	HICKORY CREEK BRIDGE	BOX CULVERTS	LIGHTING	LANDSCAPING	WATERMAIN	WATERMAIN	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	
60500040	REMOVING MANHOLES	EACH	14	14																	
60500050	REMOVING CATCH BASINS	EACH	49	49																	
60500060	REMOVING INLETS	EACH	37	37																	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	47.8	47.8																	
60600605	CONCRETE CURB, TYPE B	FOOT	777	777																	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,557	1,557																	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	59,964	59,964																	
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	1,014	1,014																	
60608521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24	FOOT	1,612	1,612																	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	15,308	15,308																	
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	6,363	6,363																	
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	6,488	6,488																	
60620200	CONCRETE MEDIAN, TYPE SB-6.24 (MODIFIED)	SQ FT	28,590	28,590																	
60624600	CORRUGATED MEDIAN	SQ FT	2,764	2,764																	
● 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	500	500																	
● 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2																	
● 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2																	
● 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2																	
● 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2																	
63200310	GUARDRAIL REMOVAL	FOOT	2,659	2,659																	
● 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2,100	2,100																	
● 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1																	
● 66900530	SOIL DISPOSAL ANALYSIS	EACH	11	11																	
● 66901000	BACKFILL PLUGS	CU YD	15	15																	
67100100	MOBILIZATION	L SUM	1	1																	
● 70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1																	
● 70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	12	12																	
● 70103817	TRAFFIC CONTROL SURVEILLANCE (SPECIAL)	CAL DA	500	500																	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	120	120																	
● 70300100	SHORT TERM PAVEMENT MARKING	FOOT	6,901	6,901																	

● INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE 2/10/2010

DRAWN BY JRR
CHECKED BY JRV