

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	(12&13)WRS-4	WILL	608	12
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

URBAN

FUNDING BREAKDOWN		80% FED 20% STATE	80% STATE 20% FPDWC	80% STATE 20% VOF	80% STATE 20% VOF	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% VOF	80% FED 20% STATE	80% FED 13.3% STATE 6.7% VOF	80% FED 10% STATE 10% FT	80% FED 10% STATE 5% VOF 5% FT	80% FED 20% STATE	80% FED 20% STATE	
LOCATION OF WORK		ROADWAY	BIKEPATH	BIKEPATH	SIDEWALK	SIDEWALK	HICKORY CREEK BRIDGE	BOX CULVERTS	LIGHTING	LANDSCAPING	WATERMAIN	WATERMAIN	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	
SUMMARY OF QUANTITIES																			
CODE NO.	PAY ITEM	UNIT	TOTAL	0003	0021	0021	0021	0021	0013	0040	0021	0031	0043	0043	0021	0021	0021	0021	0021
● 70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	400	400															
● 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	83,079	83,079															
● 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,150	1,150															
● 70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	382	382															
● 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	475	475															
● 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	88,013	88,013															
● 70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,025	2,025															
● 70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	545	545															
● 72000100	SIGN PANEL - TYPE 1	SQ FT	1,353	1,286											15	12		40	
● 72000200	SIGN PANEL - TYPE 2	SQ FT	460	272											15	30	88	55	
● 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	136	136															
● 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	7	7															
● 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	9	9															
● 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	6	6															
● 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	2,514	2,514															
● 72900100	METAL POST - TYPE A	FOOT	322	322															
● 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	10	10															
● 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	255	255															
● 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16,981	16,981															
● 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	650	650															
● 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	530	530															
● 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	42	42															
● 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	141	141															
● 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	3,706	3,706															
● 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	17,781	17,781															
● 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	17,834	17,834															
● 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	3,937	3,937															
● 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	1,278	1,278															
● 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,393	1,393															
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,461	1,461															

● INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE 6/11/2010

DRAWN BY JRR
CHECKED BY JRV