CONTRACT NO. 62478

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	(12&13)WRS-4	WILL	608	13
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

URBAN

SUMMARY OF QUANTITIES

	CODE NO.	PAY ITEM	UNIT	TOTAL	0003	0021	0021	0021	0021	0013	0040	0021	0031	0043	0043	0021	0021	0021	0021	0021	0021
		FUNDING BREAKDOWN			80% FED 20% STATE	80% STATE 20% FPDWC	80% STATE 20% VOF	80% STATE 20% VOF	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% VOF	80% FED 20% STATE	80% FED 13.3% STATE 6.7% VOF	80% FED 10% STATE 10% FT	80% FED 10% STATE 5% VOF 5% FT	80% FED 20% STATE	80% FED 20% STATE
		LOCATION OF WORK				STA. 500+85- STA. 539+79										US ROUTE 45	PFEIFFER ROAD	80TH AVENUE	FRANKFORT SQUARE	HARLEM AVENUE	INTERCONNECT
					ROADWAY	BIKEPATH	BIKEPATH	SIDEWALK	SIDEWALK	HICKORY CREEK BRIDGE	BOX CULVERTS	LIGHTING	LANDSCAPING	WATERMAIN	WATERMAIN	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS
●	78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8																
●	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2																
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	12,610	12,610																
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	331	331																
●	81000600	CONDUIT IN TRENCH, 2″ DIA., GALVANIZED STEEL	FOOT	14,806												10	650	451	524	1,065	12,106
●	81000700	CONDUIT IN TRENCH, 2½″ DIA., GALVANIZED STEEL	FOOT	10														10			
●	81000800	CONDUIT IN TRENCH, 3″ DIA., GALVANIZED STEEL	FOOT	306													129	33	43	101	
●	81001000	CONDUIT IN TRENCH, 4″ DIA., GALVANIZED STEEL	FOOT	304													38	56	116	94	
●	81018500	CONDUIT PUSHED, 2″ DIA., GALVANIZED STEEL	FOOT	2,871													100	328	241	373	1,829
●	81018600	CONDUIT PUSHED, 2½″ DIA., GALVANIZED STEEL	FOOT	26													26				
●	81018700	CONDUIT PUSHED, 3″ DIA., GALVANIZED STEEL	FOOT	41													20		21		
●	81018900	CONDUIT PUSHED, 4″ DIA., GALVANIZED STEEL	FOOT	1,905								300					216	455	356	578	
●	81100600	CONDUIT ATTACHED TO STRUCTURE, 2″ DIA., GALVANIZED STEEL	FOOT	188																	188
●	81300720	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16″ X 12″ X 8″	EACH	2																	2
●	81400100	HANDHOLE	EACH	44													4	4	4	6	26
●	81400200	HEAVY-DUTY HANDHOLE	EACH	14													2	4	4	4	
●	81400300	DOUBLE HANDHOLE	EACH	7													1	2	2	2	
●	81603177	UNIT DUCT, 600 V, 3-1/C NO. 8, 1/C NO. 8 GROUND, (EPR-TYPE RHW), 1¼″ POLYETHYLENE	FOOT	600								600									
●	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	15,464								250				10	710	524	638	1,226	12,106
●	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1												1					
●	85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	4													1	1	1	1	
●	86400100	TRANSCEIVER - FIBER OPTIC	EACH	4													1	1	1	1	
●	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,083													436	210	437		
●	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	3,472													985	556	772	1,159	
●	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	7,958													1,987	1,319	1,327	3,325	
●	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	5,668													308	1,648	1,642	2,070	
●	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	13,026												394	2,002	2,579	2,564	5,487	
●	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	130													25	36	41	28	
●	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 10 FT.	EACH	2													2				
●	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.	EACH	2													1	1			

● INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE 6/11/2010

DRAWN BY JRR

CHECKED BY JRV