

URBAN

PAY ITEM #	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 80% FEDERAL 20% STATE	BRIDGE 80% FEDERAL 20% STATE	SPECIAL BRIDGE 80% FEDERAL 20% STATE	ROADWAY 100% FRANKFORT (CEDAR RD)													
44000600	SIDEWALK REMOVAL	SQ FT	34041	0003 33879	0010	0040	0004 162													
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	521	521																
44004250	PAVED SHOULDER REMOVAL	SQ YD	2361	2361																
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	66	66																
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	297	297																
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1822	132			1690													
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1														
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1			1														
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1			1														
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1			1														
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1		1															
50100900	REMOVAL OF EXISTING STRUCTURES NO. 7	EACH	1		1															
50101000	REMOVAL OF EXISTING STRUCTURES NO. 8	EACH	1			1														
50101100	REMOVAL OF EXISTING STRUCTURES NO. 9	EACH	1			1														
50101200	REMOVAL OF EXISTING STRUCTURES NO. 10	EACH	1			1														
50101300	REMOVAL OF EXISTING STRUCTURES NO. 11	EACH	1	1																
50105220	PIPE CULVERT REMOVAL	FOOT	3174	3174																
50800105	REINFORCEMENT BARS	POUND	70563		17276	53287														
50901720	BICYCLE RAILING	FOOT	420	420																
50901750	PARAPET RAILING	FOOT	64			64														
51500100	NAME PLATES	EACH	9		1	8														
54002020	EXPANSION BOLTS 3/4 INCH	EACH	16			16														
54003000	CONCRETE BOX CULVERTS	CU YD	383.5		96.2	287.3														
54010302	PRECAST CONCRETE BOX CULVERTS 3' X 2'	FOOT	291			291														
54010303	PRECAST CONCRETE BOX CULVERTS 3' X 3'	FOOT	361			361														
54010402	PRECAST CONCRETE BOX CULVERTS 4' X 2'	FOOT	293			293														
54010403	PRECAST CONCRETE BOX CULVERTS 4' X 3'	FOOT	120.5			120.5														
54010705	PRECAST CONCRETE BOX CULVERTS 7' X 5'	FOOT	126			126														
54010804	PRECAST CONCRETE BOX CULVERTS 8' X 4'	FOOT	65			65														
54011004	PRECAST CONCRETE BOX CULVERTS 10' X 4'	FOOT	266			266														
54011210	PRECAST CONCRETE BOX CULVERTS 12' X 10'	FOOT	210		210															
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	251	251																

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
U.S. RTE. 30 (LINCOLN HIGHWAY)

SCALE : 1" = 50'
DATE : / /
DRAWN BY : BAE
CHECKED BY : GB