F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	(12&13)WRS-3	WILL	1235	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62479

URBAN

PAY ITEM #	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 80% FEDERAL 20% STATE 0003	OVER SIZED STORM SEWER SPECIAL BRIDGE 80% FEDERAL 16% STATE 4% FRANKFORT 0040
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	126	126	
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	458	458	
542A1072	PIPE CULVERTS, CLASS A, TYPE 2 27"	FOOT	162	162	
542A1087	PIPE CULVERTS, CLASS A, TYPE 2 42"	FOOT	115	115	
542A1099	PIPE CULVERTS, CLASS A, TYPE 2 54"	FOOT	123	123	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	90	90	
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	135	135	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	159	159	
542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	159	159	
5421A024	PIPE CULVERTS, CLASS A, TYPE 1 24" (TEMPORARY)	FOOT	44	44	
5421A030	PIPE CULVERTS, CLASS A, TYPE 1 30" (TEMPORARY)	FOOT	5	5	
5421A036	PIPE CULVERTS, CLASS A, TYPE 1 36" (TEMPORARY)	FOOT	58	58	
5421D015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	114	114	
5421D018	PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)	FOOT	107	107	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	34	34	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	12	12	
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	4	4	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	21	21	
54213672	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 27"	EACH	5	5	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	6	6	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1	
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	3	3	
54213699	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54"	EACH	2	2	
54213705	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 60"	EACH	1		1
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	21	21	
54247140	GRATING FOR CONCRETE FLARED END SECTION 27"	EACH	5	5	
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	6	6	
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	1	1	
54247180	GRATING FOR CONCRETE FLARED END SECTION 42"	EACH	3	3	
54247200	GRATING FOR CONCRETE FLARED END SECTION 54"	EACH	2	2	
54247210	GRATING FOR CONCRETE FLARED END SECTION 60"	EACH	1		1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

U.S. RTE. 30 (LINCOLN HIGHWAY)

SCALE : 1" = 50'
DATE : / /

DRAWN BY : BAE
CHECKED BY : GB

DLZ
ENGINEERS • ARCHITECTS • SCIENTISTS • PLANNERS • SURVEYORS
85 W. ALGONQUIN ROAD, SUITE 220 ARLINGTON HEIGHTS, IL 60005 TEL: (847) 640-0840