

PAY ITEM #	DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN			NOISE		OVER SIZED STORM SEWER			ROADWAY 100% FRANKFORT (CEDAR RD)	UTILITIES 100% NEW LENOX	UTILITIES 100% MOKENA	UTILITIES 100% FRANKFORT
				ROADWAY 80% FEDERAL 20% STATE	SPECIAL BRIDGE 80% FEDERAL 20% STATE	SPECIAL BRIDGE 80% FEDERAL 20% STATE	SPECIAL BRIDGE 80% FEDERAL 13% STATE 7% NEW LENOX	SPECIAL BRIDGE 80% FEDERAL 16% STATE 4% FRANKFORT							
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	0003	0040	0040			5						
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2	1					1						
60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	2					2							
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1	1											
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1	1											
60240305	INLETS, TYPE B, TYPE 10 FRAME AND GRATE	EACH	4	2				2							
60240312	INLETS, TYPE B, TYPE 11V FRAME AND GRATE	EACH	78	39				11	28						
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	291	214				39	38						
60240390	INLETS, TYPE B, WITH SPECIAL GRATE	EACH	2	2											
60250200	CATCH BASINS TO BE ADJUSTED	EACH	27	19						8					
60251520	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 11V FRAME AND GRATE	EACH	2	2											
60255500	MANHOLES TO BE ADJUSTED	EACH	30	28						2					
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4	4											
60260050	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	2								1	1			
60260100	INLETS TO BE ADJUSTED	EACH	1							1					
60261320	INLETS TO BE ADJUSTED WITH NEW TYPE 11V FRAME AND GRATE	EACH	10	10											
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	38								12	2	24		
60402210	GRATES, TYPE 8	EACH	1		1										
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2		2										
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	7		7										
60500040	REMOVING MANHOLES	EACH	36	36											
60500050	REMOVING CATCH BASINS	EACH	139	139											
60500060	REMOVING INLETS	EACH	15	15											
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	93	89.9						3.1					
60600605	CONCRETE CURB, TYPE B	FOOT	3373	3373											
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	634	473						161					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	77056	77056											
60614600	PAVED DITCH (SPECIAL)	FOOT	950			950									
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	5196	5196											
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	108	108											
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	710	710											
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	771	771											

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 U.S. RTE. 30 (LINCOLN HIGHWAY)
 SCALE : 1" = 50'
 DATE : / /
 DRAWN BY : BAE
 CHECKED BY : GB