

CONTRACT NO. 62479

PAY ITEM #	DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN		OVER SIZED STORM SEWER		UTILITIES 100% NEW LENOX	UTILITIES 100% MOKENA	UTILITIES 100% FRANKFORT	TRAFFIC SIGNALS									
				ROADWAY 80% FEDERAL 20% STATE	SPECIAL BRIDGE 80% FEDERAL 20% STATE	SPECIAL BRIDGE 80% FEDERAL 13% STATE 7% NEW LENOX	SPECIAL BRIDGE 80% FEDERAL 16% STATE 4% FRANKFORT				SAFETY 80% FEDERAL 10% STATE 10% NEW LENOX	SAFETY 80% FEDERAL 10% STATE 10% MOKENA	SAFETY 80% FEDERAL 10% STATE 10% FRANKFORT	SAFETY 100% FPD OF NEW LENOX	SAFETY 100% FPD OF FRANKFORT	SAFETY 80% FEDERAL 20% STATE INTERCONNECT LOCATION 1	SAFETY 80% FEDERAL 20% STATE INTERCONNECT LOCATION 2			
X4811900	AGGREGATE SHOULDERS (SPECIAL)	TON	1752	1752								0021	0021	0021	0021	0021	0021	0021	0021	
X6020088	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	15	2																
X6020096	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	7	7																
X6020098	MANHOLES, TYPE A, 9'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6				4	2												
X6025300	CATCH BASINS TO BE ADJUSTED (SPECIAL)	EACH	5	5																
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	47						22	4	21									
X6026200	INLETS TO BE ADJUSTED (SPECIAL)	EACH	10	10																
X6062100	STABILIZED MEDIAN SURFACE 12"	SO YD	834	834																
X6640200	TEMPORARY CHAIN LINK FENCE	FOOT	8416	8416																
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	24	24																
X7030104	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 4 INCH	FOOT	326305	326305																
X7030106	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 6 INCH	FOOT	20122	20122																
X7030112	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 12 INCH	FOOT	3868	3868																
X7030120	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	3920	3920																
X7030124	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 24 INCH	FOOT	1577	1577																
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	7									4	1	2						
* X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	7									4	1	2						
* X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	25338															11589	13749	
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	5602									3163	858	1581						
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	3019													1916	1103			
X0327124	PRECAST CONCRETE RISER	EACH	1		1															
X2800520	ABOVE GRADE INLET FILTERS	EACH	130	130																
K0036120	MULCH PLACEMENT 4"	SO YD	5733	5733																
X0324450	SEGMENTAL CONCRETE BLOCK WALL, SPECIAL	SQ FT	140	140																
60206705	CATCH BASINS, TYPE B	EACH	3	2			1													
35600704	HOT-MIX ASPHALT BASE COURSE WIDENING, 7"	SO YD	156	156																
* 87702162	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 14 FT. AND 52 FT.	EACH	1									1								
* 87702289	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 22 FT. AND 60 FT.	EACH	1									1								
X6041810	GRATES, TYPE 3 (SPECIAL)	EACH	1		1															
X6022930	MANHOLES, TYPE A, 5'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	1	1																
0 20076600	TRAINEES	HR	5000	5000																

0 0042  
\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
U.S. RTE. 30 (LINCOLN HIGHWAY)  
SCALE : 1" = 50'  
DATE : / /  
DRAWN BY : BAE  
CHECKED BY : GB