

ROADWAY SCHEDULE

LOCATION	31101400	Z0001055	31200502	35101800	35501308	35501316	35600708	40600625	40603080	40603080	40603310	40603310	40603310	40701861	40701956	42000416
	SUB GRAN	AGG SUBGRADE	SUB BASE	AGG BASE	HMA BASE CSE 6	HMA BASE CSE 8	HMA BC	LEV BIND MM	HMA BC IL-19.0	HMA BC IL-19.0	HMA SC "C"	HMA SC "C"	HMA SC "C"	HMA PAVT FD 9	HMA PAVT	PCC PVT 9 3/4
	MAT B 6	12 SPL	HMA 4.5	CSE B 6			WID 6 3/4"	N50 (3/4")	N50 (2 1/4")	N50 (6 3/4")	N50 (1 1/2")	N50 (2")	N50 (3")		FD 13 3/4	JOINTD
	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON	TON	SQ YD	SQ YD	SQ YD
STA 133+00 TO STA 146+00	0	7622	7622	817	0	935	0	0	0	0	0	105	137	90	0	6477
STA 146+00 TO STA 161+00	0	13761	13761	1249	303	513	0	1	0	0	38	91	210	603	0	12799
STA 161+00 TO STA 174+00	0	10112	10112	1216	336	388	0	0	0	0	0	81	204	509	0	9341
STA 174+00 TO STA 189+00	0	13133	13133	1424	53	358	0	0	0	0	0	46	239	688	0	11583
STA 189+00 TO STA 202+00	0	13043	13043	1155	59	265	36	2	0	0	44	36	194	291	0	11086
STA 202+00 TO STA 215+00	0	8988	8988	1426	73	0	0	0	0	0	0	8	240	0	0	7496
STA 215+00 TO STA 230+00	0	17699	17699	1253	619	650	0	0	0	0	0	109	210	158	0	15325
STA 230+00 TO STA 245+00	0	15408	15408	934	116	430	0	0	0	0	0	61	157	230	0	13611
STA 245+00 TO STA 260+00	0	13590	13590	1094	441	0	0	0	0	0	0	49	184	586	0	11822
STA 260+00 TO STA 275+00	0	11775	11775	1457	0	0	0	0	0	0	0	0	245	166	0	9720
STA 275+00 TO STA 290+00	0	12349	12349	1474	97	52	0	0	0	0	0	17	248	162	0	10400
STA 290+00 TO STA 303+00	0	1786	1786	220	0	46	0	0	0	0	0	5	37	0	499	1484
STA 303+00 TO STA 318+00	0	2066	2066	160	0	81	0	0	0	0	0	9	27	0	0	1569
STA 318+00 TO STA 331+00	0	11779	11779	532	0	122	0	0	0	0	0	14	89	82	0	10294
STA 331+00 TO STA 346+00	0	11575	11575	1646	0	198	0	0	0	0	0	22	277	200	0	9566
STA 346+00 TO STA 361+00	0	11136	11136	1411	0	74	0	0	0	0	0	8	237	139	0	9251
STA 361+00 TO STA 374+00	0	12900	12900	1235	0	0	0	0	0	0	0	0	208	63	0	11217
STA 374+00 TO STA 389+00	0	12582	12582	1667	0	174	0	0	0	0	0	19	280	0	0	10322
STA 389+00 TO STA 404+00	0	15214	15214	1788	141	389	0	0	0	0	0	59	300	562	0	13125
STA 404+00 TO STA 411+20	834	5790	5790	303	0	373	0	0	0	0	0	42	51	0	0	4953
ELSNER	0	219	219	0	0	0	0	0	0	0	0	0	0	0	0	201
BROOKSIDE AND HACKBERRY	0	551	551	0	214	0	0	0	0	0	0	24	0	0	0	1399
LOCUST ST.	0	0	0	0	162	39	0	0	0	0	0	23	0	1433	0	0
MARLEY RD.	0	0	0	0	51	0	0	6	0	165	148	6	0	555	0	0
SCHOOHOUSE ROAD	0	0	0	0	0	81	121	8	0	0	179	9	0	0	0	0
TALL GRASS DR.	0	0	0	0	93	0	0	0	0	0	0	10	0	447	0	0
WEST CIRCLE DR.	0	0	0	0	0	0	0	0	0	0	0	0	0	831	0	0
OWENS RD & RIDGEMORE RD	0	0	0	0	0	0	0	0	0	0	0	0	0	1156	0	0
CEDAR RD	0	0	0	0	519	0	0	0	606	0	0	598	0	0	0	0
TOTALS	834	223079	223079	22459	3277	5169	156	18	606	165	407	1452	3772	8951	499	193039

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES U.S. RTE. 30 (LINCOLN HIGHWAY) SCALE : 1" = 50' DATE : 10/12/10	DRAWN BY : BAE CHECKED BY : GB
NAME	DATE		