SCHEDULE OF QUANTITIES

PAY ITEM	UNIT	US RTE 20 @PLANK / COOMBS RD	US RTE 20 @NESTLER RD	INTERCONNECT
		Y031-1F		
CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	-	-	2615
CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	-	-	220
HANDHOLE	EACH	-	-	2
HEAVY-DUTY HANDHOLE	EACH	-	-	5
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	-	-	2615
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1	-
FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	-	1	-
TRANSCEIVER - FIBER OPTIC	EACH	1	1	-
MASTER CONTROLLER	EACH	-	-	1
DRILL EXISTING HANDHOLE	EACH	-	1	2
SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4	5	-
SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3	3	-
SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	-	1	-
SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	4	1	-
SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1	-	-
INDUCTIVE LOOP DETECTOR	EACH	-	5	-
DETECTOR LOOP REPLACEMENT	FOOT	-	376	-
RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	-	1	-
ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	-	-	3639
OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	-	-	1
UNINTERRUPTIBLE POWER SUPPLY	EACH	1	1	-
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	-	-	3639
REMOVE EXISTING SIGNAL HEAD	EACH	12	10	
CONTROLLER (SPECIAL)	EACH	1	-	-

200 22ND Street, Suite 216, Lombard, IL 60148
630.705.0110 voice, 630.839.2566 fax
WWW.MPS-IL.COM
MILLENNIA PROFESSIONAL SERVICES

DESIGNED	TVN	REVISED	-
DRAWN	TVN	REVISED	-
CHECKED	RPD	REVISED	-
DATE	4/9/2010	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US ROUTE 20 TRAFFIC SIGNAL
SCHEDULE OF QUANTITIES

SCALE: N/A | SHEET NO. 37 OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	8WRS-2	KANE	72	37

CONTRACT NO. 62529

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

P:\2009\ME09006_VarVar PhII\CADD\W05_US20\Shts\D162529-SHT-TS02-SC01.dgn

FILE NAME = P:\2009\ME09006_VarVar PhII\CADD\W05_US20\Shts\D162529-SHT-TS02-SC01.dgn
PLOT SCALE = 30.0000 ' / IN.
PLOT DATE = 4/9/2010
USER NAME = Millennia Professional Services