

PAY ITEM NUMBER	PAY ITEM NAME	UNIT	TOTAL	RECONSTRUCTION, NO CAPACITY ADDED		BRIDGE REPLACEMENT, NO CAPACITY ADDED	
				0004		0011	
51202305	DRIVING PILES	FOOT	910			910	
51203200	TEST PILE METAL SHELLS	EACH	2			2	
51204650	PILE SHOES	EACH	16			16	
51500100	NAME PLATES	EACH	1			1	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	38			38	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	2			2	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	425		425		
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4		4		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4		4		
* X 6640560	CHAIN LINK FENCE, 6' (SPECIAL)	FOOT	442		442		
X 6440300	CHAIN LINK FENCE REMOVAL	FOOT	455		455		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1			1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12		12		
67100100	MOBILIZATION	L SUM	1		1		
XX006119	TRAFFIC CONTROL AND PROTECTION (DETOUR)	L SUM	1		1		
72000100	SIGN PANEL - TYPE 1	SQ FT	7		7		
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	31		31		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3356		3356		
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	564		564		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16		16		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4		
* A2000620	TREE, ACER PLATANOIDES (NORWAY MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3		3		
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	49			49	
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	283			283	
XX004878	MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	L SUM	1		1		
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	1916		1916		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1		
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	2527			2527	
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	93			93	
Z0076600	TRAINEES	HOUR	1000		1000		

* SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED - PFR	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION GREEN GARDEN TOWNSHIP 88TH AVENUE (PEOTONE ROAD)	SUMMARY OF QUANTITIES (SHEET 2 OF 2)			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	PLOT SCALE = #SCALE#	DRAWN - PFR	REVISED -					N/A	03-07118-00-BR	WILL	43	4
TENG TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS	PLOT DATE = 10-26-2010	CHECKED - KPS	REVISED -		SCALE: N.T.S.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63156			
		DATE - 10/27/10	REVISED -									