

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTS	SIGNALS	TRAINING	NON-PARTICIPATING 100% VILLAGE OF TINLEY PARK
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE							
					004	004	021	031	021	021	042	043
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2							
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2							
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1							
	60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	1	1							
	60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	3	3							
*	60248700	VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5								5
*	60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1								1
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1							
	60255500	MANHOLES TO BE ADJUSTED	EACH	5	5							
	60260100	INLETS TO BE ADJUSTED	EACH	3	3							
	60500040	REMOVING MANHOLES	EACH	1	1							
	60500050	REMOVING CATCH BASINS	EACH	3	3							
	60500060	REMOVING INLETS	EACH	1	1							
	60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH	1	1							
	60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	2	2							
	60600605	CONCRETE CURB, TYPE B	FOOT	404	404							
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	998	998							
	60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	27	27							
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1298	1298							
	60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1860	1860							
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6							
	67100100	MOBILIZATION	L SUM	1	1							
	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1							
	X7006119	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1							
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	169	169							
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	145	145							
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2592	2592							
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	446	446							
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	104	104							
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1498	1498							
	72000100	SIGN PANEL - TYPE 1	SQ FT	11	11							
	72000200	SIGN PANEL - TYPE 2	SQ FT	25	25							
	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	8	8							
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	291	291							
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2242	2242							
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1596	1596							
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	70	70							
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	140	140							
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	545						545		
*	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	218						218		
*	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	11						11		
*	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	29						29		
*	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	153						153		
*	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	441						441		
*	81400100	HANDHOLE	EACH	4						4		
*	81400200	HEAVY-DUTY HANDHOLE	EACH	4						4		
*	81400300	DOUBLE HANDHOLE	EACH	2						2		
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1896						1896		
*	82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	2						2		

\* - INDICATES SPECIALTY ITEMS

FILE NAME = 06508-QUAN-01 - P02

USER NAME =	DESIGNED - WPD	REVISED -
	CHECKED - WPD	REVISED -
PLOT SCALE = 1"=1'	DRAWN - AG	REVISED -
PLOT DATE = 10-14-10	CHECKED - AG	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

175TH STREET AT HARLEM AVENUE  
INTERSECTION IMPROVEMENTS  
SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 5 OF 60 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	06-00104-00-CH	COOK	60	5
CONTRACT NO. 63453				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-HSP-0003 (851)				