

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTS	SIGNALS	TRAINING	NON-PARTICIPATING 100% VILLAGE OF TINLEY PARK
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE							
					004	004	021	031	021	021	042	043
	Z0076600	TRAINEES	HOUR	1000								
*	A2006618	TREE, QUERCUS IMBRICARIA (SHINGLE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5						1000	
*	X0323005	AUXILIARY VALVE AND VALVE BOX	EACH	1								1
	X0326657	RELOCATE SIGN, SPECIAL	EACH	1	1							
	X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	350	350							
	X2800510	INLET FILTER CLEANING	EACH	9	9							
	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	7	7							
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2	2							
	X4403800	MEDIAN SURFACE REMOVAL	SQ FT	1577	1577							
*	X5630006	CUT AND CAP EXISTING 6" WATER MAIN	EACH	8								8
*	X5630008	CUT AND CAP EXISTING 8" WATER MAIN	EACH	2								2
*	X5630010	CUT AND CAP EXISTING 10" WATER MAIN	EACH	2								2
	X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	5	5							
*	X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1						1		
*	X8163090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	1270						1270		
*	X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1						1		
*	X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	3400						3400		
*	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1515						1515		
*	X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	292						292		
*	XX001047	VALVE VAULTS TO BE ABANDONED	EACH	2								2
*	XX001490	GATE VALVES, 8"	EACH	2								2
*	XX003037	DUCTILE IRON FITTINGS AND ACCESSORIES	POUND	2500								2500
*	XX005855	WATER MAIN CASING PIPE	FOOT	170								170
*	XX006244	WATER SERVICE INSTALL, 2" COMPLETE	EACH	1								1
*	XX006536	WATER SERVICE LINE 1", BORED	FOOT	50								50
*	XX006879	DUCTILE IRON SOLID SLEEVE 6"	EACH	2								2
*	XX007266	FIRE HYDRANTS TO BE REMOVED, SPECIAL	EACH	2								2
*	XX007776	REMOVE AND ABANDON VALVE BOX	EACH	5								5
*	XX008209	TAPPING VALVES AND SLEEVES 10" X 8"	EACH	1								1

\* - INDICATES SPECIALTY ITEMS

FILE NAME - 06508-QUAN-01 - P04

USER NAME =	DESIGNED -- WPD	REVISED --
	CHECKED -- WPD	REVISED --
PLOT SCALE = 1=1'	DRAWN -- AG	REVISED --
PLOT DATE = 10-14-10	CHECKED -- AG	REVISED --

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

175TH STREET AT HARLEM AVENUE  
INTERSECTION IMPROVEMENTS  
SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	06-00104-00-CH	COOK	60	7
CONTRACT NO. 63453				
SCALE: NA SHEET NO. 7 OF 60 SHEETS STA. TO STA.				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-HSIP-8003 (851)				