

PAVING SCHEDULE

STA	TO	STA	LT / RT	Z0001050	35600712	40600200	40600982	40603340	40701901	40603085	44000100		X4401198	44300200	Z0062456
				AGGREGATE SUBGRADE 12"	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 11"	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	STRIP REFLECTIVE CRACK CONTROL TREATMENT	TEMPORARY PAVEMENT	(SQ YD)
				(SQ YD)	(SQ YD)	(TON)	(SQ YD)	(TON)	(SQ YD)	(TON)	(SQ YD)	(SQ YD)	(SQ YD)	(FOOT)	(SQ YD)
LILY CACHE LANE															
RECONSTRUCTION															
24+24.54		28+00.00	LT & RT	2,595.0		5.10			2,339.0		1,841.1	150.3			150.3
28+00.00		33+00.00	LT & RT	3,208.3		6.16			2,648.6		1,497.9	531.5			531.5
33+00.00		38+00.00	LT & RT	3,138.9		6.00			2,545.1		1,830.5	613.8			613.8
38+00.00		43+00.00	LT & RT	3,199.9		6.14			2,635.2		1,833.4	529.1			529.1
43+00.00		47+75.00	LT & RT	3,228.2		6.34			2,902.8		1,744.9	365.0			365.0
47+75.00		52+75.00	LT & RT	3,168.1		6.06			2,583.9		2,652.5	402.8			402.8
52+75.00		54+20.00	LT & RT	823.0		1.56			640.8		531.1	168.3			168.3
54+20.00		57+75.00	LT & RT	699.8	178.0	1.23		164.8	278.6			478.2	1,293.1	710	478.2
57+75.00		63+00.00	LT & RT	996.4	233.8	1.75		242.5	402.8			700.5	1,931.2	1,050	700.5
63+00.00		68+00.00	LT & RT	668.9	372.0	1.06		265.2	16.4			599.6	1,995.8	1,000	599.6
68+00.00		73+25.00	LT & RT	1,056.6	245.7	1.87		242.6	451.1			663.4	1,920.2	1,050	663.4
73+25.00		75+20.00	LT & RT	515.5	88.3	0.95		99.4	292.9			89.6	798.9	390	89.6
75+20.00		78+00.00	LT & RT	1,871.3		3.67			1,670.3		1,145.1	95.5			95.5
78+00.00		82+35.00	LT & RT	2,840.0		5.48			2,389.5		1,617.5	107.1			107.1
54+20.00		75+20.00	LT & RT			0.99				2,594.6					
PICARDY LANE															
200+29.00		200+75.98	LT & RT	191.1		0.38			186.3		193.6				
LINDSEY LANE															
299+42.50		299+72.50	LT & RT	214.2		0.43			212.2		267.4				
300+27.50		300+65.52	LT & RT	234.8		0.47			230.2		358.8				
PLAINVIEW DRIVE															
399+48.00		399+78.00	LT & RT	150.7		0.31			156.4		172.3				
400+22.00		400+63.25	LT & RT	219.2		0.44			218.0		194.9				
ORCHARD DRIVE															
497+25.00		497+75.00	LT & RT	24.9	5.5	0.04	140.3	16.3					140.3		
497+75.00		499+67.00	LT & RT	819.8		1.61			734.3		608.8				
500+18.00		501+00.00	LT & RT	363.3		0.73			347.9		337.6				
501+00.00		501+22.00	LT & RT	86.2		0.13	81.3	9.1					81.2		
FROM ENTRANCE SCHEDULE						2.00									
TOTALS				30,314.1	1,123.3	60.90	221.6	1,039.9	23,882.3	2,594.6	16,827.4	5,494.7	8,160.7	4,200	5,494.7
USE				30,315	1,124	61	222	1,040	23,883	2,595	22,323	8,161	4,200	5,495	