

TREE SCHEDULE

LOCATION	OFFSET	RT/LT	DIAMETER (INCHES)	20100110 TREE REMOVAL (6 TO 15 UNITS DIA)	20100210 TREE REMOVAL (OVER 15 UNITS DIA)	20101000 TEMPORARY FENCE	20101200 TREE ROOT PRUNING	K0026610 TRANSPLANTED SALVAGED TREES	A2008722 TREE, ULMUS PATRIOT (PATRIOT ELM) 2" CALIPER, BALLED AND BURLAPPED	A2006420 TREE, QUERCUS ALBA (WHITE OAK), 2 1/2" CALIPER, BALLED AND BURLAPPED	A2004514 TREE, GINKGO BILOBA AUTUMN GOLD (AUTUMN GOLD GINKGO), 2 1/2" CALIPER, BALLED AND BURLAPPED	A2004620 TREE, GLEDITSIA TRIACANTHOS INERMIS (THORNLESS COMMON HONEYLOCUST), 2 1/2" CALIPER, BALLED AND BURLAPPED	ROOT BARRIER	Z0055000 RUBBLE STONE TREE WELL
				(UNIT)	(UNIT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)
LILY CACHE LANE														
60+86	38'	LT	4					1						
60+93	33'	RT									1			
61+02	27'	RT	18		18									
61+24	34'	RT									1			
61+25	27'	RT	30		30									
61+41	32'	LT	18		18									
61+46	30'	LT								1				
61+56	34'	RT	8											1
61+96	33'	RT	8			13								1
62+08	30'	LT								1				
62+08	39'	LT	8	8										
62+33	33'	RT	8			13								
62+72	33'	RT	8			13								
62+89	30'	LT								1				
62+90	32'	LT	30		30									
63+12	32'	RT	8			13								
63+50	34'	LT	10	10										
63+52	30'	LT								1				
63+53	33'	RT	8			13								
63+93	33'	RT	8			13								
64+21	33'	LT	24		24									
64+24	30'	LT								1				
64+32	33'	RT	8			13								
64+35	33'	LT	8	8										
64+72	33'	RT	8	8										
64+84	32'	LT	30		30									
65+84	40'	LT	4					1						
66+13	41'	LT	6					1						
66+21	33'	RT	6					1						
66+30	30'	LT										1	1	
66+38	41'	LT	6					1						
66+53	39'	LT	6					1						
66+60	33'	RT	6					1						
66+65	30'	LT												
66+73	70'	LT	6					1		1				
67+00	30'	LT								1				
67+01	33'	RT	4			7								1
67+15	40'	LT	6					1						
67+35	40'	LT	6					1						
67+41	33'	RT	10			16								1
67+51	30'	LT								1				
67+54	40'	LT	6					1						
67+66	38'	RT	4					1						
67+81	33'	LT	8			13								
67+96	32'	LT	15	15										
67+98	30'	LT								1				