

UTILITY ADJUSTMENT & REMOVAL SCHEDULE						
STATION	OFFSET	LT / RT	60255500 MANHOLES TO BE ADJUSTED	60266600 VALVE BOXES TO BE ADJUSTED	X8140115 HANDHOLE TO BE ADJUSTED	X8950810 REMOVE AND RE-ERECT FLASHING BEACON
	(FEET)		(EACH)	(EACH)	(EACH)	(EACH)
24+36	5	LT	1			
26+01	23	RT				
26+72	46	LT				
27+03	2	LT	1			
27+19	31	LT	1			
27+90	26	RT				
29+21	33	LT	1			
31+87	49	LT	1			
32+31	50	LT	1			
34+10	50	LT	1			
34+60	34	LT	1			
34+68	34	LT	1			
36+18	43	LT	1			
38+95	42	LT	1			
43+36	34	LT	1			
44+56	35	RT	1			
44+75	38	RT			1	
44+92	28	RT	1			
44+93	43	LT	1			
45+52	33	RT		1		
45+60	29	LT				
45+70	38	RT			1	
48+94	37	RT	1			
46+26	19	RT				1
51+16	33	LT	1			
51+79	37	RT		1		
52+95	45	LT	1			
53+69	31	RT		1		
53+90	38	LT	1			
54+54	47	LT	1			
55+08	20	RT				
56+39	24	LT				1
58+16	46	LT	1			
58+31	20	RT				
58+92	32	LT	1			
59+78	39	LT	1			
65+06	20	LT		1		
65+06	39	LT	1			
65+16	26	LT				
65+23	56	RT				
66+85	34	LT	1			
68+26	23	RT				
69+14	46	LT	1			
72+48	24	RT				1
72+59	46	LT	1			
75+14	37	LT	1			
75+38	29	LT				
75+48	40	RT				
75+87	26	RT		1		
75+93	50	LT	1			
78+65	29	LT				1
TOTAL			29	5	2	4

ESTIMATED QUANTITY SCHEDULE		
PAY CODE	DESCRIPTION	QUANTITY
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	940 SQ YD
45100200	CRACK FILLING	500 POUND

RETAINING WALL REMOVAL SCHEDULE				
STA.	TO	STA.	LT / RT	Z0075505 TIMBER RETAINING WALL REMOVAL
				(FOOT)
60+77		61+59	RT	86
TOTALS				86