



PR ☐ LILY CACHE LANE

**NOTE:**  
ALL NEW SIGNS AND EXISTING SIGNS SHOWN TO BE RELOCATED SHALL BE PLACED IN THEIR PERMANENT LOCATIONS AS DIRECTED BY THE ENGINEER.

**LANDSCAPING LEGEND**

- INDICATES PROPOSED SODDING AREAS
- PROPOSED TREES  
SEE "GENERAL NOTES FOR TREE PLANTING AND LANDSCAPING" FOR APPROVED TREES AND INSTRUCTIONS.
- EXISTING TREES  
INDICATES TEMPORARY FENCE (SEE TREE SCHEDULE FOR ADDITIONAL WORK)
- INDICATES TRANSPLANTED SALVAGED TREES
- INDICATES TREE REMOVAL

**PAVEMENT MARKING LEGEND**

- ① THERMOPLASTIC PAVEMENT MARKING - LINE 4", SOLID WHITE
- ② THERMOPLASTIC PAVEMENT MARKING - LINE 4", SOLID YELLOW
- ③ THERMOPLASTIC PAVEMENT MARKING - LINE 4", WHITE SKIP-DASH (10' LINE - 30' SKIP) (TYP)
- ④ THERMOPLASTIC PAVEMENT MARKING - LINE 4", YELLOW SKIP-DASH (10' LINE - 30' SKIP) (TYP)
- ⑤ THERMOPLASTIC PAVEMENT MARKING - LINE 4", DOUBLE SOLID YELLOW
- ⑥ THERMOPLASTIC PAVEMENT MARKING - LINE 6", SOLID WHITE
- ⑦ THERMOPLASTIC PAVEMENT MARKING - LINE 6", WHITE DOTTED (2' LINE - 6' SKIP) (TYP)
- ⑧ THERMOPLASTIC PAVEMENT MARKING - LINE 12", SOLID WHITE
- ⑨ THERMOPLASTIC PAVEMENT MARKING - LINE 12", SOLID YELLOW
- ⑩ THERMOPLASTIC PAVEMENT MARKING - LINE 24", SOLID WHITE
- ⑪ THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS (8' TYP)

FILE NAME = G:\S09021\CADD_Sheets\9021FS02.dgn	USER NAME = IE Consultants	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>LILY CACHE LANE SIGNING, PAVEMENT MARKING &amp; LANDSCAPING PLAN</b>			F.A.U.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 20,000' / IN.	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA. 28+00	TO STA. 33+00	1578	06-00046-01-PV	WILL
PLOT DATE = 10/22/2010	DATE -	REVISOR -	REVISOR -					ILLINOIS FED. AID PROJECT		CONTRACT NO. 63503		