



NOTE:
ALL NEW SIGNS AND EXISTING SIGNS SHOWN TO BE RELOCATED SHALL BE PLACED IN THEIR PERMANENT LOCATIONS AS DIRECTED BY THE ENGINEER.

LANDSCAPING LEGEND

- INDICATES PROPOSED SODDING AREAS
- PROPOSED TREES
SEE "GENERAL NOTES FOR TREE PLANTING AND LANDSCAPING" FOR APPROVED TREES AND INSTRUCTIONS.
- EXISTING TREES
INDICATES TEMPORARY FENCE (SEE TREE SCHEDULE FOR ADDITIONAL WORK)
- INDICATES TRANSPLANTED SALVAGED TREES
- INDICATES TREE REMOVAL

PAVEMENT MARKING LEGEND

- ① THERMOPLASTIC PAVEMENT MARKING - LINE 4", SOLID WHITE
- ② THERMOPLASTIC PAVEMENT MARKING - LINE 4", SOLID YELLOW
- ③ THERMOPLASTIC PAVEMENT MARKING - LINE 4", WHITE SKIP-DASH (10' LINE - 30' SKIP) (TYP)
- ④ THERMOPLASTIC PAVEMENT MARKING - LINE 4", YELLOW SKIP-DASH (10' LINE - 30' SKIP) (TYP)
- ⑤ THERMOPLASTIC PAVEMENT MARKING - LINE 4", DOUBLE SOLID YELLOW
- ⑥ THERMOPLASTIC PAVEMENT MARKING - LINE 6", SOLID WHITE
- ⑦ THERMOPLASTIC PAVEMENT MARKING - LINE 6", WHITE DOTTED (2' LINE - 6' SKIP) (TYP)
- ⑧ THERMOPLASTIC PAVEMENT MARKING - LINE 12", SOLID WHITE
- ⑨ THERMOPLASTIC PAVEMENT MARKING - LINE 12", SOLID YELLOW
- ⑩ THERMOPLASTIC PAVEMENT MARKING - LINE 24", SOLID WHITE
- ⑪ THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS (8' TYP)

FILE NAME = G:\S09021\CADD_Sheets\9021F908.dgn	USER NAME = IE Consultants	DESIGNED -	REVISD -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	LILY CACHE LANE SIGNING, PAVEMENT MARKING & LANDSCAPING PLAN				F.A.U.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 20,0000' / IN.	CHECKED -	REVISD -	REVISD -		SCALE:	SHEET NO.	OF	SHEETS	STA. 57+75	TO STA. 63+00	WILL	244	187
PLOT DATE = 10/22/2010	DATE -	REVISD -	REVISD -		ILLINOIS FED. AID PROJECT								
											CONTRACT NO. 63503		