

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	ROADWAY 75%FEDERAL 25%STATE 0003	SIGNALS 75%FEDERAL 25%STATE 0021	DUNDEE RD 75%FEDERAL 25%STATE 0003	WATER MAIN SANITARY 100% LOCAL 0043
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	152	48		104	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	162	72		90	
20101100	TREE TRUNK PROTECTION	EACH	19	5		14	
20101200	TREE ROOT PRUNING	EACH	17	6		11	
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	8	1		7	
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	11	3		8	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	23,714	20,762		2,952	
20400800	FURNISHED EXCAVATION	CU YD	242	140		102	
20800150	TRENCH BACKFILL	CU YD	13,448	7,477		300	5,671
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	12,946	12,946			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	13,100	5,628		7,472	
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	600	600			
25000115	SEEDING, CLASS 1B	ACRE	2.75	1.21		1.54	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	245	106		139	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	245	106		139	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	245	106		139	
25100630	EROSION CONTROL BLANKET	SO YD	13,160	5,688		7,472	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	272	117		155	
28000305	TEMPORARY DITCH CHECKS	FOOT	192			192	
28000400	PERIMETER EROSION BARRIER	FOOT	1,360			1,360	
28000500	INLET AND PIPE PROTECTION	EACH	12	1		11	
28000510	INLET FILTERS	EACH	90	79		11	
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SO YD	9,320	9,320			
35600718	HOT-MIX ASPHALT BASE COURSE WIDENING, 10 1/2"	SO YD	1,690			1,690	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	1,004	854		150	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,305	744		561	
40600300	AGGREGATE (PRIME COAT)	TON	27	15		12	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	323			323	
40600895	CONSTRUCTING TEST STRIP	EACH	2	1		1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	235	180		55	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	873	873			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	855			855	
40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SO YD	21,285	21,285			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	1,155	1,155			
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	130	130			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	50,650	45,215		5,435	
42400800	DETECTABLE WARNINGS	SO FT	390	370		20	
44000100	PAVEMENT REMOVAL	SO YD	21,035	21,035			
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SO YD	7,460	7,460			
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	3,790	3,215		575	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,920	2,278		642	
44000600	SIDEWALK REMOVAL	SO FT	6,810	5,934		876	
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SO YD	395	225		170	
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SO YD	265	115		150	
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SO YD	135	60		75	
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SO YD	135	60		75	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	310			310	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	2,650			2,650	
550A0050	STORM SEWERS, CLASS A, TYPE 1 1/2"	FOOT	882	588		294	
550A0070	STORM SEWERS, CLASS A, TYPE 1 1/5"	FOOT	112			112	

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	ROADWAY 75%FEDERAL 25%STATE 0003	SIGNALS 75%FEDERAL 25%STATE 0021	DUNDEE RD 75%FEDERAL 25%STATE 0003	WATER MAIN SANITARY 100% LOCAL 0043
550A0090	STORM SEWERS, CLASS A, TYPE 1 1/8"	FOOT	56			56	
550A0160	STORM SEWERS, CLASS A, TYPE 1 3/8"	FOOT	6			6	
550A0190	STORM SEWERS, CLASS A, TYPE 1 4/8"	FOOT	24	24			
550A0340	STORM SEWERS, CLASS A, TYPE 2 1/2"	FOOT	46	39		7	
550A0380	STORM SEWERS, CLASS A, TYPE 2 1/8"	FOOT	376			376	
550A0410	STORM SEWERS, CLASS A, TYPE 2 2/4"	FOOT	1,078	1,078			
550A0430	STORM SEWERS, CLASS A, TYPE 2 3/0"	FOOT	2,887	2,887			
550A0450	STORM SEWERS, CLASS A, TYPE 2 3/6"	FOOT	1,191	734		457	
550A0480	STORM SEWERS, CLASS A, TYPE 2 4/8"	FOOT	24	24			
550A4300	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	216	216			
55100300	STORM SEWER REMOVAL 8"	FOOT	16			16	
55100500	STORM SEWER REMOVAL 12"	FOOT	81	60		21	
55201600	STORM SEWERS JACKED IN PLACE, 48"	FOOT	131	131			
56106400	ADJUSTING WATER MAIN 8"	FOOT	67	67			
56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	1,320	1,320			
56300200	ADJUSTING SANITARY SEWERS, OVER 8-INCH DIAMETER	FOOT	536	536			
56300300	ADJUSTING WATER SERVICE LINES	FOOT	33	33			
56400100	FIRE HYDRANTS TO BE MOVED	EACH	6	6			
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	8				8
56400700	FIRE HYDRANTS (SPECIAL)	EACH	16				16
60107600	PIPE UNDERDRAINS 4"	FOOT	3,296			3,296	
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE B GRATE	EACH	7			7	
60201110	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE IIV FRAME AND GRATE	EACH	24	22		2	
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE B GRATE	EACH	4			4	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	6	5		1	
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	31	31			
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	3	2		1	
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	2			2	
60236700	INLETS, TYPE A, TYPE 10 FRAME AND GRATE	EACH	2			2	
60236825	INLETS, TYPE A, TYPE IIV FRAME AND GRATE	EACH	54	52		2	
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1			1	
60240305	INLETS, TYPE B, TYPE 10 FRAME AND GRATE	EACH	2			2	
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE I FRAME, CLOSED LID	EACH	1	1			
60266910	VALVE BOXES TO BE REMOVED	EACH	20				20
60405700	FRAMES AND GRATES, SPECIAL	EACH	1	1			
60500040	REMOVING MANHOLES	EACH	1	1			
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	7			7	
60600605	CONCRETE CURB, TYPE B	FOOT	395	143		252	
60602800	CONCRETE GUTTER, TYPE B	FOOT	1,276			1,276	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	11,765	11,743		22	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	175			175	
66900205	SPECIAL WASTE DISPOSAL	CU YD	200	100		100	
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	95			95	
66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1			1	
66900530	SOIL DISPOSAL ANALYSIS	EACH	2			2	
67100100	MOBILIZATION	L SUM	1	1			
XX008438	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			

† SPECIALTY ITEM  
• SPECIAL PROVISION

COMPANY NAME: SEC GROUP, INC.  
PROJECT CONTACT: A. JAIN  
VILLAGE OF CARPENTERSVILLE  
DATE PLOTTED: 11/6/2010 8:59 PM  
FILE NAME: 08026-Sub-01.dgn  
PLOT SCALE: 1/8"=1'-0"  
PEN TABLE: Standard-Trans.tbl

**SEC Group, Inc.**  
An HR Group Company  
200 N. First Street  
Melrose, IL 60052-2130  
TEL: 815.381.1770 FAX: 815.381.1771  
www.secgroup.com  
Melrose, IL • Naperville, IL • New Lenox, IL • Chicago, IL

USER NAME = CHor-the	DESIGNED - J. ATTANASEO	REVISED -
PLOT SCALE = N.T.S.	DRAWN - R. BEST	REVISED -
PLOT DATE = 11/6/2010	CHECKED - T. HAMILTON	REVISED -
	DATE - 10/25/10	REVISED -

**VILLAGE OF CARPENTERSVILLE**

**SUMMARY OF QUANTITIES**

SCALE: N.T.S. SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	06-0074-00-FP	KANE	211	4
*FAU 2414, FAU 1280, FAP 343			CONTRACT NO. 63504	
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				