

INDEX OF SHEETS

- 1. COVER SHEET
- 2. INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
- 3. SUMMARY OF QUANTITIES
- 4. SCHEDULE OF QUANTITIES
- 5.-17. SIGNING PLANS
- 18.-19. SIGNING DETAILS
- 20. ILLUMINATED STREET SIGN LOCATION MAP
- 21.-50. ILLUMINATED STREET SIGN PLANS
- 51.-54. STREET NAME SIGNS
- 55. CONSTRUCTION DETAILS

STATE STANDARDS

- 000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 701601-07 URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
- 701606-07 URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
- 701701-07 URBAN LANE CLOSURE MULTILANE INTERSECTION
- 701801-04 LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
- 701901-01 TRAFFIC CONTROL DEVICES
- 720001-01 SIGN PANEL MOUNTING DETAILS

GENERAL NOTES

- 1. BEFORE ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)
- 2. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY OWNERS AND THE VILLAGE OF BRIDGEVIEW, PALOS HILLS AND CHICAGO RIDGE.
- 3. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON VILLAGE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE VILLAGE OF BRIDGEVIEW.
- 4. THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2007 BY THE ILLINOIS DEPARTMENT OF TRANSPORTATION, AND THE LATEST SUPPLEMENTAL SPECIFICATIONS SHALL GOVERN THIS WORK.
- 5. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- 6. THE CONTRACTOR SHALL PROTECT ALL EXISTING PLANT MATERIAL FROM DAMAGE FOR WHICH THE CONTRACT DOES NOT PROVIDE REMOVAL. THE PROTECTION OF EXISTING PLANT MATERIAL AND THE REPAIR OR REPLACEMENT OF EXISTING PLANT MATERIAL DAMAGED BY THE CONTRACTOR SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION 201 OF THE STANDARD SPECIFICATIONS UNLESS OTHERWISE NOTED.
- 7. THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847)-705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.
- 8. THE APPROXIMATE LOCATION OF KNOWN PUBLIC UTILITIES ARE SHOWN ON THE PLANS.
- 9. HOWEVER, THE DEPARTMENT DOES NOT GUARANTEE THEIR ACCURACY. PRIOR TO COMMENCING OPERATIONS ON THE PROJECT WHICH MAY IN ANY WAY CREATE THE POSSIBILITY OF INVOLVEMENT WITH EXISTING UTILITIES, THE CONTRACTOR SHALL CONTACT THE UTILITY OWNER (OR COMMUNITY) INVOLVED. ADJUSTMENT OF ALL PUBLIC UTILITIES WITHIN THE LIMITS OF THIS IMPROVEMENT WILL BE DONE BY THE RESPECTIVE OWNERS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY LOCATIONS OF UNDERGROUND INSTALLATION BEFORE STARTING CONSTRUCTION OPERATIONS IN ACCORDANCE WITH SPECIAL PROVISION LR105. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH ALL UTILITY COMPANIES.

| | | | | | | | | | | | | |
|---|---------------|-----------------|---|---|--|--------------------------|------|---------------|--------------|--------|-----------------|--------------|
| FILE NAME = 07441_02-NOTE-01 - IDOT P01 | USER NAME = | DESIGNED -- MRS | REVISED -- | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | HARLEM AVENUE BEAUTIFICATION FROM SOUTHWEST HIGHWAY TO 65TH STREET INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES | | | F.A.P. RTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | | CHECKED -- PKB | REVISED -- | | 348 | 07-00055-01-SG | COOK | 55 | 2 | | | |
| PLOT SCALE = | DRAWN -- RG | REVISED -- | SCALE: NONE | | | SHEET NO. 2 OF 55 SHEETS | | | STA. TO STA. | | | |
| PLOT DATE = 10-21-10 | CHECKED -- AG | REVISED -- | FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT HPP-3462(001) CONTRACT NO. 63510 | | | | | | | | | |