

SUMMARY OF QUANTITIES				SIGNAL QUANTITIES ALONG HUNTLEY ROAD					SIGNAL QUANTITIES ALONG RANDALL ROAD					INTERCONNECT QUANTITIES		
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SQUARE BARN ROAD	BOYER ROAD	ACCESS ROAD	MILLER ROAD	SLEEPY HOLLOW ROAD	BINNIE ROAD	MILLER ROAD	HUNTLEY ROAD	CORPORATE PARKWAY	COMMONS DRIVE	COUNTY LINE ROAD	HUNTLEY ROAD	RANDALL ROAD
CONSTRUCTION CODE - 0021																
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8					8								
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	26	10				16								
88500100	INDUCTIVE LOOP DETECTOR	EACH	3	2				1								
88600100	DETECTOR LOOP, TYPE 1	FOOT	336	96				48							96	96
88700200	LIGHT DETECTOR	EACH	7	3				4								
88700300	LIGHT DETECTOR AMPLIFIER	EACH	2	1				1								
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8					8								
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	22		1	3	2		2	2	3	3	3	3		
89502500	REMOVE TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2	1				1								
X0322283	VIDEO SURVEILLANCE SYSTEM COMPLETE	EACH	4	1				1	1		1					
X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	631	326				305								
X0325476	RADAR VEHICLE DETECTION SYSTEM	EACH	1	1												
X0325961	TRACER CABLE NO. 14 1/C	FOOT	26264												18018	8246
X0326452	VIDEO SYSTEM DETECTION PROCESSOR	EACH	4			1	1				1			1		
X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	470					470								
X7800650	URETHANE PAVEMENT MARKING - LINE 12"	FOOT	73					73								
X7800680	URETHANE PAVEMENT MARKING - LINE 24"	FOOT	94					94								
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	3			1	1			1						
X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	9	1		1		1	1	1	1	1	1	1		
X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	27915												19675	8240
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1431	671				760								
XX007950	FIBER OPTIC PIGTAIL	EACH	88												44	44
XX007953	NETWORK CONFIGURATION	L SUM	1												0.5	0.5
XX007994	FIBER OPTIC SPLICE	EACH	12												4	8
XX008253	VIDEO ENCODER	EACH	2									1	1			
Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	11	1	1	1	1	1	1	1	1	1	1	1		
Z0033054	CONFIRMATION BEACON	EACH	20						4	4		4	4	4		
Z0033072	VIDEO VEHICLE DETECTION SYSTEM	EACH	2									1	1			
Δ Z0076600	TRAINEES	hour	500													
<del>XX008453</del>	ETHERNET SWITCH, TYPE 1	EACH	10	1	1	1	1	1	1	1		1	1	1		
<del>XX008454</del>	ETHERNET SWITCH, TYPE 2	EACH	1								1					
X8710029	FIBER OPTIC 24F SM	FOOT	2629													2629
<del>XX007139</del>	<del>Wireless</del> VEHICLE DETECTION SYSTEM - COMPLETE	EACH	1					1								
<del>XX008452</del>	MALFUNCTION MANAGEMENT UNIT	EACH	11	1	1	1	1	1	1	1	1	1	1	1		
<del>X0326714</del>	MODIFY EXISTING <del>CONTROLLER CABINET SPECIAL</del>	EACH	2				1									
<del>XX008459</del>	VIDEO CAMERA INTERFACE MODULE	EACH	4				1					1		1		
<del>XX008479</del>	VIDEO ENCODER, TYPE 1	EACH	4				1					1		1		

Δ = 0042