

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0005	0021	0021	0021	0031	0043
				RECONSTRUCTION, NO CAPACITY ADDED	SYSTEM PRESERVATION, RESURFACING	SAFETY (TRAFFIC SIGNALS)	SAFETY (LIGHTING)	SAFETY (SIDEWALKS)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	NON-PARTICIPATING
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	6	6						
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2						
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3						
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	9	9						
60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	1	1						
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1						
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1						
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1		1					
60261540	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1						
● X6026622	VALVE VAULTS TO BE REMOVED	EACH	1							1
● 60266600	VALVE BOXES TO BE ADJUSTED	EACH	1							1
60500050	REMOVING CATCH BASINS	EACH	1	1						
60500060	REMOVING INLETS	EACH	14	13	1					
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	4	4						
60600605	CONCRETE CURB, TYPE B	FOOT	279	279						
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	298	288	10					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1743	1743						
60605400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)	FOOT	1023	1023						
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	1803		1803					
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1397		1397					
X6061900	CONCRETE MEDIAN, TYPE SB-6.12 (SPECIAL)	SQ FT	1783	1783						
60620800	CONCRETE MEDIAN, TYPE SB-9.12	SQ FT	146		146					
60624600	CORRUGATED MEDIAN	SQ FT	119	119						
⚠ 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1600	1600						
● 66900205	SPECIAL WASTE DISPOSAL	CU YD	322	322						
● 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1						
⚠ 66900530	SOIL DISPOSAL ANALYSIS	EACH	7	7						
● 66900565	PNAS SOIL ANALYSIS	EACH	2	2						
● 66900590	RCRA METALS TCLP SOIL ANALYSIS	EACH	1	1						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9						
67100100	MOBILIZATION	L SUM	1	1						
● X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1						
● XX008438	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1						
● 70106800	CHANGEABLE MESSAGE SIGN	CAL MO	36	36						
● 70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8177	2623	5554					
● 70300210	TEMPORARY PAVEMENT MARKING- LETTERS AND SYMBOLS	SQ FT	290	73	217					

Revised 1/13/2011, Addendum B

● SPECIALTY ITEM

FILE NAME =	USER NAME = djc	DESIGNED - BLG Addendum B	REVISED - 01-10-2011	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
...Addendum\2363_Sum_Quant.dgn		DRAWN - BLG	REVISED -			334	09-00057-00-CH	COOK	103	6	
		CHECKED - DJK	REVISED -			CONTRACT NO. 63523					
		DATE - 10-22-10	REVISED -			SHEET NO. 3 OF 7 SHEETS					
						FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003660					