



**NOTES:**

1. ALL SURFACES SHALL BE FLUSH WITH EXISTING RAILS.
2. THE PAY ITEM "SIDEWALK RAILROAD CROSSING" SHALL INCLUDE THE CONSTRUCTION OF THE 7" P.C.C. PAD BETWEEN THE RAILS AND THE CONSTRUCTION OF THE 7" P.C.C. SIDEWALK, DETECTABLE WARNINGS, AND 6" SUB-BASE GRANULAR MATERIAL AS SHOWN ABOVE.
3. ANY BALLAST REMOVAL REQUIRED TO CONSTRUCT THE RAILROAD CROSSING SHALL BE INCLUDED IN THE COST OF THE PAY ITEM "SIDEWALK RAILROAD CROSSING".
4. ALL MATERIAL SHALL BE APPROVED BY THE ENGINEER PRIOR TO THEIR INSTALLATION.
5. THE CONTRACTOR SHALL COORDINATE ALL CONSTRUCTION ACTIVITIES RELATED TO THE CONSTRUCTION OF THE RAILROAD CROSSING WITH THE RAILROAD COMPANY.

**SIDEWALK RAILROAD CROSSING DETAIL**

FILE NAME = ...\\ood\sheet\2363.detail.02.dgn	USER NAME = djc	DESIGNED - BLG	REVISED -
		DRAWN - BLG	REVISED -
		CHECKED - DJK	REVISED -
		DATE - 10-22-10	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**ROADWAY DETAILS**

SHEET NO. 2 OF 3 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
334	09-00057-00-CH	COOK	103	71
<b>CONTRACT NO. 63523</b>				

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003(660)