

EARTHWORK SCHEDULE - GREENLEAF AVENUE				
ITEM	UNIT	STAGE 1	STAGE 2	STAGE 3
EARTH EXCAVATION	C.Y.	478	564	574
EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	C.Y.	407	480	488
EMBANKMENT REQUIRED	C.Y.	349	836	44
EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	C.Y.	+58	-356	+444

EARTHWORK SCHEDULE - IL ROUTE 83 (BUSSE ROAD)				
ITEM	UNIT	STAGE 1	STAGE 2	STAGE 3
EARTH EXCAVATION	C.Y.	-	-	678
EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	C.Y.	-	-	576
EMBANKMENT REQUIRED	C.Y.	-	-	76
EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	C.Y.	-	-	+500

SHRINKAGE CALCULATED USING 15% SHRINKAGE FACTOR

A PAY ITEM FOR "FURNISHED EXCAVATION" HAS BEEN INCLUDED ON THE ASSUMPTION THAT, DUE TO LIMITED WORKING SPACE, ALL EMBANKMENT MAY HAVE TO BE BROUGHT IN FROM OUTSIDE THE PROJECT LIMITS.

SCHEDULE OF TREE REMOVAL	
STATION	6 TO 15 UNIT DIAMETER
124+80, LT	7
124+91, RT	6
125+07, LT	6
128+05, LT	8

SCHEDULE OF DRIVEWAY PAVEMENT REMOVAL & REPLACEMENT		
STATION	DRIVEWAY PAVEMENT REMOVAL	PCC DW, 8", SPECIAL
109+72, RT	2 SY	2 SY
110+60, RT	36 SY	36 SY
111+24, LT	27 SY	30 SY
111+51, RT	50 SY	61 SY
111+68, LT	33 SY	37 SY
112+41, RT	53 SY	54 SY
113+61, RT	45 SY	57 SY
114+20, LT	79 SY	92 SY
114+73, RT	42 SY	48 SY
115+39, LT	40 SY	52 SY
115+81, RT	70 SY	100 SY
116+75, LT	51 SY	114 SY
116+82, RT	56 SY	59 SY
117+22, LT*	52 SY	0 SY
117+35, RT	51 SY	48 SY
121+38, LT	58 SY	65 SY
122+53, LT	98 SY	143 SY
122+63, RT	65 SY	67 SY
123+06, LT**	45 SY	0 SY
123+22, RT	37 SY	43 SY
124+47, RT	43 SY	52 SY
126+68, LT	45 SY	131 SY
127+13, LT***	35 SY	0 SY
127+39, RT	164 SY	171 SY
129+05, RT	41 SY	38 SY

* PROPOSED DRIVEWAY AREA COMBINED WITH DRIVEWAY AT 116+75, LT

** PROPOSED DRIVEWAY AREA COMBINED WITH DRIVEWAY AT 122+53, LT

*** PROPOSED DRIVEWAY AREA COMBINED WITH DRIVEWAY AT 126+68, LT

FILE NAME =
...oad\sheet\2362.schedule.dgn

USER NAME = blg

DESIGNED - JAT

REVISED -

DRAWN - JAT

REVISED -

PLOT SCALE = 50.0000' / IN.

CHECKED - DJK

REVISED -

PLOT DATE = 10/22/2010

DATE - 10-22-10

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SHEET NO. 1 OF 1 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
334	09-00056-00-CH	COOK	111	15
CONTRACT NO. 63527				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003659				