SUMMARY OF QUANTITIES

CODE NO.	ITEMS	UNIT	QUANTITY (0004)
20101100	TREE TRUNK PROTECTION	EACH	40
20200100	EARTH EXCAVATION	CU YD	1327
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	30
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	100
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,937
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	24
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	24
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	24
25200110	SODDING, SALT TOLERANT	SQ YD	1,937
25200200	SUPPLEMENTAL WATERING	UNIT	6
28000510	INLET FILTERS	EACH	10
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	5,161
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	50
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	932
35800100	PREPARATION OF BASE	SQ YD	1,506
35800200	AGGREGATE BASE REPAIR	TON	65
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,048
40600300	AGGREGATE (PRIME COAT)	TON	13
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	52
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	193
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	236
40701801	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"	SQ YD	4071
42001300	PROTECTIVE COAT	SQ YD	1,264
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	191
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	525
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,902
42400800	DETECTABLE WARNINGS	SQ FT	184
44000100	PAVEMENT REMOVAL	SQ YD	4258
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	1506
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,083
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,000
44000600	SIDEWALK REMOVAL	SQ FT	1,639
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	1,505
60251520	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 11V FRAME AND GRATE	EACH	8
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	10
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	12

CODE NO.	ITEMS	UNIT	QUANTITY (0004)
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	3,028
67100100	MOBILIZATION	L SUM	1
X7010216	TRAFFIC CONTROL AND PROTECTION	L SUM	1
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	395
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	114
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	12
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	16
X6026056	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	30

* SPECIALTY ITEMS